



Lumber design values are in accordance with ANSI/TPI 1 section 6.3
These truss designs rely on lumber values established by others.

RE: 2584809 - CHRISMILL HOMES - TODD RES.

MiTek USA, Inc.
6904 Parke East Blvd.
Tampa, FL 33610-4115

Site Information:

Customer Info: Chrismill Homes Project Name: Todd Res. Model: Custom
Lot/Block: N/A Subdivision: N/A
Address: TBD, TBD
City: Columbia Cty State: FL

Name Address and License # of Structural Engineer of Record, If there is one, for the building.


Name: License #:
Address:
City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: FBC2020/TPI2014 Design Program: MiTek 20/20 8.4
Wind Code: N/A Wind Speed: 130 mph
Roof Load: 37.0 psf Floor Load: N/A psf

This package includes 47 individual, Truss Design Drawings and 0 Additional Drawings.
With my seal affixed to this sheet, I hereby certify that I am the Truss Design Engineer and this conforms to 61G15-31.003, section 5 of the Florida Board of Professional Engineers Rules.


No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	T22973341	CJ01	2/25/21	15	T22973355	PB07	2/25/21
2	T22973342	CJ03	2/25/21	16	T22973356	T01G	2/25/21
3	T22973343	CJ05	2/25/21	17	T22973357	T02	2/25/21
4	T22973344	EJ01	2/25/21	18	T22973358	T02A	2/25/21
5	T22973345	EJ02	2/25/21	19	T22973359	T02G	2/25/21
6	T22973346	EJ03	2/25/21	20	T22973360	T03	2/25/21
7	T22973347	HJ09	2/25/21	21	T22973361	T04	2/25/21
8	T22973348	HJ10	2/25/21	22	T22973362	T05	2/25/21
9	T22973349	PB01	2/25/21	23	T22973363	T06	2/25/21
10	T22973350	PB02	2/25/21	24	T22973364	T07	2/25/21
11	T22973351	PB03	2/25/21	25	T22973365	T08	2/25/21
12	T22973352	PB04	2/25/21	26	T22973366	T09	2/25/21
13	T22973353	PB05	2/25/21	27	T22973367	T10	2/25/21
14	T22973354	PB06	2/25/21	28	T22973368	T11	2/25/21



This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature.
Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies

The truss drawing(s) referenced above have been prepared by
MiTek USA, Inc. under my direct supervision based on the parameters
provided by Builders FirstSource-Jacksonville.

Truss Design Engineer's Name: Velez, Joaquin
My license renewal date for the state of Florida is February 28, 2023.



Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

February 25, 2021

Velez, Joaquin

1 of 2



RE: 2584809 - CHRISMILL HOMES - TODD RES.

MiTek USA, Inc.
6904 Parke East Blvd.
Tampa, FL 33610-4115

Site Information:

Customer Info: Chrismill Homes Project Name: Todd Res. Model: Custom
Lot/Block: N/A Subdivision: N/A
Address: TBD, TBD
City: Columbia Cty State: FL

No.	Seal#	Truss Name	Date
29	T22973369	T12	2/25/21
30	T22973370	T13	2/25/21
31	T22973371	T14	2/25/21
32	T22973372	T15	2/25/21
33	T22973373	T16	2/25/21
34	T22973374	T17	2/25/21
35	T22973375	T18	2/25/21
36	T22973376	T19	2/25/21
37	T22973377	T20	2/25/21
38	T22973378	T21	2/25/21
39	T22973379	T22	2/25/21
40	T22973380	T23	2/25/21
41	T22973381	T24	2/25/21
42	T22973382	T24G	2/25/21
43	T22973383	T25	2/25/21
44	T22973384	T26G	2/25/21
45	T22973385	T27	2/25/21
46	T22973386	T27G	2/25/21
47	T22973387	T28	2/25/21

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	CJ01	Jack-Open	6	1	T22973341
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,
8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:03 2021 Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-5YHeHleVJQNJoyLUMJezc79n8bmcUCbcaAai2Jzhywc




Plate Offsets (X,Y)--		[2:0-1-13,0-1-0]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.10	Vert(LL)	0.00	7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.02	Vert(CT)	0.00	7	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	2	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 6 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 1-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-5-8, 4=Mechanical
Max Horz 2=47(LC 12)
Max Uplift 3=3(LC 12), 2=55(LC 12), 4=13(LC 1)
Max Grav 3=6(LC 8), 2=157(LC 1), 4=17(LC 16)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2, 4.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021



Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973342
2584809	CJ03	Jack-Open	6	1		

Builders FirstSource (Jacksonville, FL),


Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:04 2021 Page 1

ID:l32pVj5BVg?fJzzugcSEYRy57kM-Zlr0U5f74kVAQ5wgv09C8Kiyu?53DfrpqqJGamzhywb

-1-4-0
1-4-0
3-0-0
3-0-0

Scale = 1:16.7



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.10	Vert(LL)	-0.00	4-7	>999	240	MT20
TCDL 7.0	Lumber DOL	1.25	BC 0.07	Vert(CT)	-0.01	4-7	>999	180	244/190
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						
								Weight: 12 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=91(LC 12)
Max Uplift 3=-43(LC 12), 2=-41(LC 12)
Max Grav 3=66(LC 19), 2=197(LC 1), 4=51(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610


Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973343
2584809	CJ05	Jack-Open	5	1		
Job Reference (optional)						

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:05 2021 Page 1

ID:l32pVj5BVg?fJzzugcSEYRy57kM-2xPPiRglq2d12FVtUkhRhYE4iOPby65v1U3p6Czhywa



Scale = 1:23.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.29	Vert(LL)	0.03	4-7	>999	240	MT20
TCDL 7.0	Lumber DOL	1.25	BC 0.25	Vert(CT)	-0.06	4-7	>999	180	244/190
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						
									Weight: 19 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-5-8, 4=Mechanical
Max Horz 2=135(LC 12)
Max Uplift 3=-79(LC 12), 2=-41(LC 12), 4=-1(LC 12)
Max Grav 3=121(LC 19), 2=264(LC 1), 4=90(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2, 4.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job 2584809	Truss EJ01	Truss Type Jack-Partial	Qty 26	Ply 1	CHRISMILL HOMES - TODD RES. T22973344
Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244, 8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:05 2021 Page 1 ID: i32pVj5BVg?iJzzugcSEYRy57kM-2xPPiRglq2d12FVtUkhRhYE3hOMYy5tv1U3p6Czhywa					
Job Reference (optional)					




Plate Offsets (X,Y)--		[2:0-1-9,0-2-5]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL 20.0	Plate Grip DOL	1.25	TC 0.36	Vert(LL)	-0.08	6-9	>999	240	MT20	244/190	
TCDL 7.0	Lumber DOL	1.25	BC 0.44	Vert(CT)	-0.16	6-9	>527	180			
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.08	Horz(CT)	0.00	2	n/a	n/a			
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS								
										Weight: 31 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS.	
(size)	4=Mechanical, 2=0-5-8, 5=Mechanical
Max Horz	2=180(LC 12)
Max Uplift	4=-57(LC 12), 2=-44(LC 12), 5=-58(LC 12)
Max Grav	4=75(LC 19), 2=336(LC 1), 5=186(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2, 5.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

MiTek
6904 Parke East Blvd.
Tampa, FL 33610


Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973345
2584809	EJ02	Jack-Open	2	1		
Job Reference (optional)						

Builders FirstSource (Jacksonville, FL),


Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:06 2021 Page 1

ID:132pVj5BVg?fJzzugcSEYRy57kM-W7znvngNbLiufP431RCgElnHeolchZL2G8oMeezhwyZ



Scale = 1:19.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.15	Vert(LL)	-0.01	4-7	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.13	Vert(CT)	-0.02	4-7	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 15 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-5-8, 4=Mechanical
Max Horz 2=109(LC 12)
Max Uplift 3=58(LC 12), 2=40(LC 12)
Max Grav 3=89(LC 19), 2=224(LC 1), 4=67(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	EJ03	Jack-Open Girder	1	1	T22973346
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,
8.430 s Feb 12 2021 MiTek Industries, Inc.
Wed Feb 24 09:55:07 2021
Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-_JW967h?MftlHZfB9jvmzKQAC1RQ0bBVoYwB5zhywY




Plate Offsets (X,Y)--		[2:0-3-7,0-0-8]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d		PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.29	Vert(LL)	-0.03	4-6	>999	240		MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.41	Vert(CT)	-0.05	4-6	>883	180			
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	2	n/a	n/a			
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP							Weight: 19 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-10-0 oc purlins.
BOT CHORD	2x6 SP M 26	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS. (size) 1=0-5-8, 4=Mechanical, 2=Mechanical
Max Horz 1=79(LC 8)
Max Uplift 1=-117(LC 8), 4=-128(LC 8), 2=-57(LC 8)
Max Grav 1=706(LC 2), 4=703(LC 2), 2=109(LC 29)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Refer to girder(s) for truss to truss connections.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 1=117, 4=128.
 - Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1275 lb down and 250 lb up at 1-10-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-2=-54, 1-3=-20

Concentrated Loads (lb)

Vert: 7=-1170(F)

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


February 25,2021




Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	HJ09	Diagonal Hip Girder	1	1	T22973347

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,
8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:08 2021 Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-SW4XKTid7z?cvjES9sE8JAsbmcO_9RXLkSHTjXzhywX



Scale = 1:25.3



LOADING (psf)		SPACING-		CSI.		DEFL.		I/defl		L/d		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.30	Vert(LL)	-0.02	6-7	>999	240		MT20		244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.33	Vert(CT)	-0.04	6-7	>999	180					
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.15	Horz(CT)	0.00	5	n/a	n/a					
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS											
												Weight: 38 lb		FT = 20%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3		

REACTIONS. (size) 4=Mechanical, 2=0-4-9, 5=Mechanical
Max Horz 2=153(LC 8)
Max Uplift 4=89(LC 8), 2=-142(LC 4), 5=-113(LC 5)
Max Grav 4=133(LC 1), 2=342(LC 19), 5=238(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-447/169
BOT CHORD 2-7=-212/345, 6-7=-212/345
WEBS 3-6=-387/237

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 2=142, 5=113.
 - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 58 lb down and 57 lb up at 1-6-1, 58 lb down and 57 lb up at 1-6-1, 77 lb down and 46 lb up at 4-4-0, and 77 lb down and 46 lb up at 4-4-0, and 101 lb down and 89 lb up at 7-1-15 on top chord, and 37 lb down and 44 lb up at 1-6-1, 37 lb down and 44 lb up at 1-6-1, 47 lb down at 4-4-0, and 47 lb down at 4-4-0, and 67 lb down and 16 lb up at 7-1-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)
Vert: 1-4=-54, 5-8=-20
Concentrated Loads (lb)
Vert: 11=115(F=57, B=57) 13=-50(F) 15=-8(F=-4, B=-4) 16=-35(F)

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021




Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	HJ10	Diagonal Hip Girder	2	1	T22973348
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:09 2021 Page 1

ID:l32pVj5BVg?fJzzugcSEYRy57kM-wievXpjGuG7TWtpejalNrOPhg0gEurdUy611FzzyWw



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.61	Vert(LL)	-0.05	6-7	>999	240	MT20
TCDL 7.0	Lumber DOL	1.25	BC 0.59	Vert(CT)	-0.11	6-7	>999	180	244/190
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.35	Horz(CT)	0.01	5	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						
									Weight: 45 lb FT = 20%

LUMBER-			BRACING-	
TOP CHORD	2x4 SP No.2		TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2		BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3			

REACTIONS.	(size)	4=Mechanical, 2=0-7-6, 5=Mechanical
	Max Horz	2=179(LC 8)
	Max Uplift	4=104(LC 8), 2=152(LC 8), 5=108(LC 8)
	Max Grav	4=152(LC 1), 2=417(LC 1), 5=297(LC 3)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=670/191
BOT CHORD	2-7=271/536, 6-7=271/536
WEBS	3-7=0/287, 3-6=586/296

- NOTES-**
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 4=104, 2=152, 5=108.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 58 lb down and 57 lb up at 1-6-1, 58 lb down and 57 lb up at 1-6-1, 77 lb down and 46 lb up at 4-4-0, 77 lb down and 46 lb up at 4-4-0, and 107 lb down and 90 lb up at 7-1-15, and 107 lb down and 90 lb up at 7-1-15 on top chord, and 15 lb down and 44 lb up at 1-6-1, 15 lb down and 44 lb up at 1-6-1, 25 lb down at 4-4-0, 25 lb down at 4-4-0, and 47 lb down and 16 lb up at 7-1-15, and 47 lb down and 16 lb up at 7-1-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)	Standard
1) Dead + Roof Live (balanced):	Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)	
	Vert: 1-4=-54, 5-8=-20
Concentrated Loads (lb)	
	Vert: 7=-8(F=-4, B=-4) 11=115(F=57, B=57) 12=-75(F=-38, B=-38) 14=-62(F=-31, B=-31)

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


February 25,2021

Job 2584809	Truss PB01	Truss Type Piggyback	Qty 5	Ply 1	CHRISMILL HOMES - TODD RES. T22973349
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:10 2021 Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-OuCll8jufaGK80OqGHGcObyxOP6kdNMeBlmanQzhywV



Scale = 1:24.3

Plate Offsets (X,Y)--		[2:0-3-9,0-1-8], [4:0-3-9,0-1-8]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 20.0	Plate Grip DOL 1.25	TC 0.29	in (loc) l/defl L/d
TCDL 7.0	Lumber DOL 1.25	BC 0.25	Vert(LL) 0.01 5 n/r 120
BCLL 0.0 *	Rep Stress Incr YES	WB 0.06	Vert(CT) 0.02 5 n/r 120
BCDL 10.0	Code FBC2020/TPI2014	Matrix-S	Horz(CT) 0.00 4 n/a n/a
		Weight: 40 lb FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS.

(size) 2=10-1-12, 4=10-1-12, 6=10-1-12
Max Horz 2=79(LC 11)
Max Uplift 2=-56(LC 12), 4=-66(LC 13), 6=-48(LC 12)
Max Grav 2=210(LC 1), 4=210(LC 1), 6=382(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4, 6.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 33610


Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973350
2584809	PB02	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:10 2021 Page 1

ID:132pVj5BVg?fJzzugcSEYRy57kM-OuCl8jufaGK80OqGHGcObyzCP8jdNleBlmanQzhywV



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.18	Vert(LL)	0.00	6	n/r	120	MT20
TCDL 7.0	Lumber DOL	1.25	BC 0.12	Vert(CT)	0.01	6	n/r	120	244/190
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	5	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						
								Weight: 43 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

- All bearings 10-1-12.
(lb) - Max Horz 2=64(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2, 5, 7, 8
Max Grav All reactions 250 lb or less at joint(s) 2, 5 except 7=254(LC 24), 8=254(LC 23)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 5, 7, 8.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 33610

Job 2584809	Truss PB03	Truss Type Piggyback	Qty 1	Ply 1	CHRISMILL HOMES - TODD RES. T22973351
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:11 2021 Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-s5mgyUkWQuOBmAy1q?nrwpU8epUFMq0nQPW7KszhywU




Plate Offsets (X,Y)--		[2:0-3-9,0-1-8], [3:0-3-0,0-2-3], [4:0-3-0,0-2-3], [5:0-3-9,0-1-8]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.13
TCDL 7.0	Lumber DOL	1.25	BC 0.10
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-S
		DEFL. in (loc) l/def L/d Vert(LL) 0.00 6 n/r 120 Vert(CT) 0.00 6 n/r 120 Horz(CT) 0.00 5 n/a n/a	
		PLATES	GRIP
		MT20	244/190
		Weight: 40 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 10-1-12.
(lb) - Max Horz 2=52(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2, 5, 7, 8
Max Grav All reactions 250 lb or less at joint(s) 2, 5 except 7=272(LC 24), 8=272(LC 23)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TC DL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 5, 7, 8.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	PB04	Piggyback	1	1	T22973352
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244, 8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:12 2021 Page 1
ID:I32pVj5BVg?fJzzugcSEYRy57kM-LHK2Aql8BBW2OKXDOiJ4T01KuDqx5Hlxe3FhsizhywT




Plate Offsets (X,Y)-- [2:0-3-9,0-1-8], [3:0-3-0,0-2-3], [5:0-3-0,0-2-3], [6:0-3-9,0-1-8]					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	PLATES GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.10	Vert(LL) 0.00 6 n/r 120	MT20 244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.07	Vert(CT) 0.00 6 n/r 120	
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT) 0.00 6 n/a n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S		Weight: 39 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 10-1-12.
(lb) - Max Horz 2=35(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 2, 6, 8, 10, 9
Max Grav All reactions 250 lb or less at joint(s) 2, 6, 8, 10 except 9=254(LC 24)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 6, 8, 10, 9.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	PB05	GABLE	1	1	T22973353
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:13 2021 Page 1
ID:132pVj5BVg?fJzzugcSEYRy57kM-pTuQNAmmYVev?U6PyPqJ0EZVXd9oqkY4tj?EOkzhywS

2-0-0
2-0-0

9-8-0
7-8-0

11-8-0
2-0-0

Scale = 1:20.2




Plate Offsets (X,Y)-- [2:0-3-9,0-1-8], [3:0-3-5,Edge], [6:0-3-5,Edge], [7:0-3-9,0-1-8]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	20.0	Plate Grip DOL	1.25	TC	0.11	Vert(LL)	0.00	7	n/r	120	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.10	Vert(CT)	0.00	8	n/r	120		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	7	n/a	n/a		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-S							Weight: 35 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS	2x4 SP No.3		

REACTIONS. All bearings 10-1-12.
(lb) - Max Horz 2=23(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 2, 7, 9, 10
Max Grav All reactions 250 lb or less at joint(s) 2, 7 except 9=266(LC 24), 10=266(LC 23)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 4-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 7, 9, 10.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021


Job 2584809	Truss PB06	Truss Type Piggyback	Qty 5	Ply 1	CHRISMILL HOMES - TODD RES. T22973354
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:14 2021 Page 1

ID: i32pVj5BVg?fJzzugcSEYRy57kM-HgSoaWnOjpmmdhebv7LYYR6fq1WiZB2D6NknwBzhywR



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.07	Vert(LL)	0.00	5	n/r	120	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.05	Vert(CT)	0.00	5	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.02	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-P						Weight: 20 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=4-7-12, 4=4-7-12, 6=4-7-12
Max Horz 2=-40(LC 10)
Max Uplift 2=-37(LC 12), 4=-43(LC 13), 6=-9(LC 12)
Max Grav 2=120(LC 1), 4=120(LC 1), 6=155(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4, 6.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 33610


6904 Parke East Blvd
Tampa, FL 36610

Job 2584809	Truss T01G	Truss Type Common Supported Gable	Qty 1	Ply 1	CHRISMILL HOMES - TODD RES. T22973356
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:16 2021 Page 1

ID: i32pVj5BVg?fJzzugcSEYRy57kM-D2ZZ?CofFQ0Tsxr_dYN0dsB?tqCY15QWZhDu?3zhywP



Scale = 1:27.0




Plate Offsets (X,Y)--		[2:0-3-8,Edge], [10:0-3-8,Edge]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL	1.25	TC 0.10		Vert(LL)	-0.00 11	n/r	120	MT20	244/190
TCDL 7.0		Lumber DOL	1.25	BC 0.03		Vert(CT)	-0.01 11	n/r	120		
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.03		Horz(CT)	0.00 10	n/a	n/a		
BCDL 10.0		Code FBC2020/TPI2014		Matrix-S						Weight: 67 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 12-0-0.
(lb) - Max Horz 2=97(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 2, 10, 15, 16, 13, 12
Max Grav All reactions 250 lb or less at joint(s) 2, 10, 14, 15, 16, 13, 12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 10, 15, 16, 13, 12.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2, 10.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T02	COMMON	8	1	T22973357

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021
MiTek Industries, Inc.
Wed Feb 24 09:55:17 2021
Page 1
ID:I32pVj5BVg?fJzzugcSEYRy57kM-hF7xDYpH0k8KU5QABFuFA4k5iEJ_mPjgoLzSXWzhywO

-1-4-0
1-4-0

7-0-0
7-0-0

12-0-0
5-0-0

17-0-0
5-0-0

24-0-0
7-0-0

25-4-0
1-4-0

4x6 ||

Scale = 1:51.7




Plate Offsets (X,Y)-- [2:0-6-12,0-0-11], [3:0-3-0,0-3-0], [5:0-3-0,0-3-0], [6:0-6-12,0-0-11]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.42	Vert(LL)	-0.23	8-10	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.98	Vert(CT)	-0.43	8-10	>675	180		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.60	Horz(CT)	0.03	6	n/a	n/a		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS							Weight: 144 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-9-2 oc purlins.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	

REACTIONS.	(size) 2=0-5-8, 6=0-5-8
	Max Horz 2=-190(LC 10)
	Max Uplift 2=-270(LC 12), 6=-270(LC 13)
	Max Grav 2=1386(LC 19), 6=1386(LC 20)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-2110/383, 3-4=-2138/538, 4-5=-2138/538, 5-6=-2110/383
BOT CHORD	2-10=-327/1806, 8-10=-131/1111, 6-8=-230/1699
WEBS	4-8=-359/1298, 5-8=-338/244, 4-10=-359/1298, 3-10=-338/244

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TC DL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=-270, 6=270.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)	Standard
1) Dead + Roof Live (balanced):	Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)	
Vert:	1-4=-54, 4-7=-54, 2-10=-20, 8-10=-80(F=-60), 6-8=-20

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T02G	GABLE	1	1	T22973359
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244, 8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:19 2021 Page 1
ID:132pVj5BVg?fJzzugcSEYRy57kM-ddFheDqXXLO2jPaZlgxjFVpRS29rEM?zFfSYcOzhywM




Plate Offsets (X,Y)-- [5:0-2-0,0-0-0], [14:0-4-0,0-4-8]											
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES GRIP			
TCLL	20.0	Plate Grip DOL	1.25	TC	0.40	Vert(LL)	-0.04 10-39	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.31	Vert(CT)	-0.08 10-39	>999	180		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.42	Horz(CT)	0.01 8	n/a	n/a		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS						Weight: 207 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing, Except:
WEBS 2x4 SP No.3	10-0-0 oc bracing: 8-10.
OTHERS 2x4 SP No.3	WEBS 1 Row at midpt 5-15

REACTIONS.	All bearings 12-5-8 except (jt=length) 8=0-5-8, 11=0-3-8.
(lb) - Max Horz	2=-183(LC 10)
Max Uplift	All uplift 100 lb or less at joint(s) 17, 11 except 8=-155(LC 13), 15=-277(LC 12), 12=-435(LC 20), 16=-150(LC 23)
Max Grav	All reactions 250 lb or less at joint(s) 12, 13, 16 except 8=634(LC 20), 15=1101(LC 1), 17=315(LC 19), 11=601(LC 20)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-4=-127/531, 4-5=0/499, 5-6=-674/308, 6-8=-614/151
BOT CHORD	2-17=-410/198, 16-17=-410/198, 15-16=-410/198, 8-10=-14/465
WEBS	5-10=-269/733, 6-10=-370/241, 5-15=-817/118, 4-15=-331/233

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 5) All plates are 2x4 MT20 unless otherwise indicated.
 - 6) Gable studs spaced at 2-0-0 oc.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 17, 11 except (jt=lb) 8=155, 15=277, 12=435, 16=150.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T03	Monopitch	4	1	T22973360
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,
8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:20 2021 Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-6qp4rZr9IfWvLZ8lsOSyoiMciRTuzrX6UJB68qzhywL



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.43	Vert(LL)	-0.06	6-9	>999	240	MT20
TCDL 7.0	Lumber DOL	1.25	BC 0.39	Vert(CT)	-0.13	6-9	>935	180	244/190
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.27	Horz(CT)	0.01	2	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						
									Weight: 61 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-5-8, 5=0-3-8

Max Horz 2=251(LC 12)

Max Uplift 2=49(LC 12), 5=-171(LC 12)

Max Grav 2=452(LC 1), 5=387(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-371/0

WEBS 3-6=0/267, 3-5=-448/200

NOTES-

- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 5=171.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182

MiTek USA, Inc. FL Cert 6634

6904 Parke East Blvd. Tampa FL 33610

Date:

February 25,2021



Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973361
2584809	T04	Flat Girder	1	1	Job Reference (optional)	

NOTES-
 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
 Uniform Loads (plf)
 Vert: 1-7=-54, 8-16=-20
 Concentrated Loads (lb)
 Vert: 7=-42(F) 15=-158(F) 2=-18(F) 10=-158(F) 17=-18(F) 18=-18(F) 19=-18(F) 20=-18(F) 21=-18(F) 22=-18(F) 23=-18(F) 24=-18(F) 25=-18(F) 26=-18(F) 27=-18(F) 28=-18(F) 29=-18(F) 30=-18(F) 31=-158(F) 32=-158(F) 33=-158(F) 34=-158(F) 35=-158(F) 36=-158(F) 37=-158(F) 38=-158(F) 39=-158(F) 40=-158(F) 41=-158(F) 42=-158(F) 43=-158(F)

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T05	Half Hip	1	1	T22973362

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:25 2021 Page 1
ID:l32pVj5BVg?fJzzugcSEYRy57kM-SncyuHvl7B8CRK1jfx27Vm3QiS4Se?qrebvtp2zhywG

4-8-3
4-8-3

9-0-0
4-3-13

16-5-9
7-5-9

24-0-15
7-7-5

31-10-0
7-9-1

Scale = 1:55.2




Plate Offsets (X,Y)--		[1:0-8-0,0-0-12], [3:0-3-4,Edge]									
LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES	
TCLL	20.0	Plate Grip DOL	2-0-0	TC	0.61	in (loc)	l/defl	L/d		MT20	GRIP
TCDL	7.0	Lumber DOL	1.25	BC	0.81	Vert(LL)	-0.14 11-13	>999	240		244/190
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.65	Vert(CT)	-0.28 13-16	>999	180		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS		Horz(CT)	0.07 8	n/a	n/a		
										Weight: 180 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-10-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 9-4-1 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midpt 7-8, 4-13, 4-9
REACTIONS.			
(size) 1=Mechanical, 8=0-3-8			
Max Horz 1=197(LC 12)			
Max Uplift 1=179(LC 9), 8=293(LC 9)			
Max Grav 1=1292(LC 2), 8=1333(LC 2)			

FORCES.			
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.			
TOP CHORD	1-2=-1953/328, 2-3=-1797/328, 3-4=-1445/294, 4-6=-1351/299, 6-7=-1351/299, 7-8=-1184/311		
BOT CHORD	1-13=-353/1609, 11-13=-397/1833, 9-11=-397/1833		
WEBS	2-13=-257/165, 3-13=-65/717, 4-13=-558/198, 4-11=0/382, 4-9=-611/124, 6-9=-440/205, 7-9=-372/1684		

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=179, 8=293.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T06	Half Hip	1	1	T22973363

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:26 2021 Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-wzAL6dwwuVH33UcvCeZM1zcc7sUFNQK_sFeQMuzhywF

5-6-0

11-0-0

18-0-5

25-6-4

33-0-3

40-4-0

5-6-0

5-6-0

7-0-5

7-5-15

7-5-15

7-3-13

Scale = 1:69.8




Plate Offsets (X,Y)-- [1:0-6-0,0-0-8], [3:0-3-4,Edge]													
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP			
TCLL	20.0	Plate Grip DOL	1.25	TC	0.56	Vert(LL)	-0.33	9-10	>999	240	MT20	244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.52	Vert(CT)	-0.55	9-10	>876	180			
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.83	Horz(CT)	0.10	9	n/a	n/a			
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS								Weight: 237 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-4-13 oc purlins, except end verticals.
BOT CHORD 2x4 SP M 31	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 4-14, 6-10
OTHERS 2x4 SP No.3	2 Rows at 1/3 pts 7-9
REACTIONS.	
(size) 1=Mechanical, 9=0-3-8	
Max Horz 1=241(LC 12)	
Max Uplift 1=232(LC 9), 9=372(LC 9)	
Max Grav 1=1661(LC 2), 9=1715(LC 2)	

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-2645/414, 2-3=-2329/427, 3-4=-1874/378, 4-6=-2398/488, 6-7=-1807/364
BOT CHORD	1-15=-439/2154, 14-15=-439/2154, 12-14=-511/2349, 10-12=-486/2209, 9-10=-320/1413
WEBS	2-14=-409/199, 3-14=-125/996, 4-14=-745/260, 6-12=-36/362, 6-10=-731/222, 7-10=-129/1133, 7-9=-1981/452

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=232, 9=372.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T08	Hip	1	1	T22973365

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:28 2021 Page 1

ID:l32pVj5BVg?fJzzugcSEYRy57kM-tMI5WlxAQ6XmInmIK3bq7OhtPg6MrN1HKZ7XQNzhywD

7-5-6

15-0-0

20-10-0

26-8-0

34-2-10

40-4-0

7-5-6

7-6-10

5-10-0

5-10-0

7-6-10

6-1-6

Scale = 1:73.0




Plate Offsets (X,Y)--		[1:0-6-0,0-0-4], [2:0-4-0,0-3-0], [3:0-4-0,0-1-9], [5:0-4-0,0-1-9], [6:0-3-0,0-3-4]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 20.0	Plate Grip DOL 2-0-0	TC 0.83	in (loc) l/defl L/d
TCDL 7.0	Lumber DOL 1.25	BC 0.80	Vert(LL) -0.15 12-13 >999 240
BCLL 0.0 *	Rep Stress Incr YES	WB 0.63	Vert(CT) -0.26 13-15 >999 180
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS	Horz(CT) 0.10 8 n/a n/a
		PLATES GRIP	
		MT20 244/190	
		Weight: 255 lb FT = 20%	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 8-5-13 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 2-13, 4-12, 6-11

REACTIONS.	(size) 1=Mechanical, 8=0-3-8
Max Horz 1=210(LC 9)	
Max Uplift 1=296(LC 12), 8=287(LC 13)	
Max Grav 1=1639(LC 2), 8=1643(LC 2)	

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-2560/463, 2-3=-2017/413, 3-4=-1712/377, 4-5=-1712/376, 5-6=-1929/389, 6-7=-2143/383, 7-8=-1550/300
BOT CHORD	1-15=-455/2131, 13-15=-455/2130, 12-13=-233/1592, 11-12=-138/1523, 9-11=-253/1734
WEBS	2-15=0/314, 2-13=-679/267, 3-13=-105/652, 3-12=-177/348, 4-12=-368/175, 5-12=-181/462, 5-11=-73/484, 6-11=-359/201, 7-9=-221/1643

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCdL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=296, 8=287.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


February 25,2021

Job 2584809	Truss T10	Truss Type Piggyback Base	Qty 2	Ply 1	CHRISMILL HOMES - TODD RES. T22973367
Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,					

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:30 2021 Page 1
ID: l32pVj5BVg?fJzzugcSEYRy57kM-plPrx_zRyjnUY5vgRUdlCpnCkToJJ1antceVFzhywB

1-4-0	7-5-6	15-0-0	20-10-0	26-8-0	34-2-10	41-8-0	43-0-0
1-4-0	7-5-6	7-6-10	5-10-0	5-10-0	7-6-10	7-5-6	1-4-0

Scale = 1:75.6



	7-5-6	15-0-0	20-10-0	26-8-0	34-2-10	41-8-0	
	7-5-6	7-6-10	5-10-0	5-10-0	7-6-10	7-5-6	

Plate Offsets (X,Y)-- [2:0-6-0,0-0-8], [3:0-4-0,0-3-0], [4:0-6-4,0-2-4], [6:0-6-4,0-2-4], [7:0-4-0,0-3-0], [8:0-6-0,0-0-7]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.84	Vert(LL)	-0.17 10-12	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.80	Vert(CT)	-0.32 10-12	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.46	Horz(CT)	0.13 8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS					Weight: 256 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 8-9-10 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 3-14, 5-13, 7-12

REACTIONS. (size) 2=0-5-8, 8=0-5-8
Max Horz 2=233(LC 10)
Max Uplift 2=330(LC 12), 8=330(LC 13)
Max Grav 2=1756(LC 2), 8=1756(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2654/468, 3-4=-2095/418, 4-5=-1802/387, 5-6=-1802/387, 6-7=-2095/418, 7-8=-2654/469
BOT CHORD 2-16=-429/2216, 14-16=-429/2216, 13-14=-207/1663, 12-13=-120/1663, 10-12=-272/2147, 8-10=-272/2148
WEBS 3-16=0/320, 3-14=-699/268, 4-14=-102/657, 4-13=-181/387, 5-13=-347/171, 6-13=-181/387, 6-12=-102/657, 7-12=-699/269, 7-10=0/320

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=330, 8=330.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component


Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 33610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T11	Piggyback Base	3	1	T22973368

Builders FirstSource (Jacksonville, FL),		Jacksonville, FL - 32244,		8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:32 2021 Page 1		
ID:I32pVj5BVg?fJzzugcSEYRy57kM-I7XcMg_hUL1CnP33ZvgmHEsbKHUjnDutFB5kZ8zhyw9						
1-4-0	7-5-6	15-0-0	20-10-0	26-8-0	34-2-10	41-8-0
1-4-0	7-5-6	7-6-10	5-10-0	5-10-0	7-6-10	7-5-6



LOADING (psf)		SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL 1.25	TC 0.65	Vert(LL) -0.12 9-23 >999 240	MT20	244/190
TCDL 7.0		Lumber DOL 1.25	BC 0.71	Vert(CT) -0.23 9-23 >999 180		
BCLL 0.0 *		Rep Stress Incr YES	WB 0.51	Horz(CT) 0.05 8 n/a n/a		
BCDL 10.0		Code FBC2020/TPI2014	Matrix-MS		Weight: 270 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-7-5 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 14-16.
BOT CHORD	2x4 SP No.2	BOT CHORD	
WEBS	2x4 SP No.3	WEBS	1 Row at midpt 3-16, 4-14, 5-13, 6-13, 7-12
REACTIONS.			
	(size) 2=0-3-8, 16=0-5-8, 8=Mechanical		
	Max Horz 2=227(LC 9)		
	Max Uplift 2=-107(LC 12), 16=-298(LC 12), 8=-262(LC 13)		
	Max Grav 2=558(LC 25), 16=1610(LC 2), 8=1310(LC 20)		

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-528/125, 3-4=-846/230, 4-5=-986/304, 5-6=-986/304, 6-7=-1382/350, 7-8=-1932/408
BOT CHORD	2-17=-198/423, 16-17=-198/423, 14-16=-537/204, 13-14=-123/633, 12-13=-61/1070, 10-12=-230/1597, 9-10=-248/1565, 8-9=-248/1565
WEBS	3-17=-85/256, 3-16=-1745/369, 3-14=-111/1327, 4-14=-543/95, 4-13=-172/789, 5-13=-350/172, 6-13=-267/97, 6-12=-110/651, 7-12=-747/256, 7-9=0/264

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCdL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=107, 16=298, 8=262.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021


Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973369
2584809	T12	Hip Girder	1	1		

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021
MiTek Industries, Inc.
Wed Feb 24 09:55:34 2021
Page 1
ID:132pVj5BVg?fJzzugcSEYRy57kM-hWfMnM0x?yHw0iDRgKiEMfx_34GXF32AiUare0zhyw7

-1-4-0
1-4-0
3-11-4
3-11-4
7-0-0
3-0-12
11-4-5
4-4-5
16-1-0
4-8-11
20-9-11
4-8-11
25-2-0
4-4-5
28-2-12
3-0-12
32-2-0
3-11-4
33-6-0
1-4-0

Scale = 1:56.7



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.50	Vert(LL)	0.23 15-17	MT20	244/190		
TCDL	7.0	Lumber DOL	1.25	BC	0.36	Vert(CT)	-0.38 12-14	MT20HS	187/143		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.72	Horz(CT)	0.09 10				
BCDL	10.0	Code	FBC2020/TPI2014	Matrix-MS							
								Weight: 204 lb FT = 20%			

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 2-6-3 oc purlins.
BOT CHORD	2x6 SP M 26	BOT CHORD	Rigid ceiling directly applied or 7-5-2 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midpt 5-17, 7-12

REACTIONS. (size) 2=0-5-8, 10=0-5-8
Max Horz 2=119(LC 25)
Max Uplift 2=912(LC 8), 10=946(LC 9)
Max Grav 2=2415(LC 1), 10=2458(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3976/1551, 3-4=-3823/1531, 4-5=-3202/1322, 5-6=-4487/1822, 6-7=-4504/1825, 7-8=-3264/1372, 8-9=-3899/1592, 9-10=-4053/1613
BOT CHORD 2-17=-1286/3260, 15-17=-1656/4121, 14-15=-1831/4571, 12-14=-1655/4154, 10-12=-1257/3324
WEBS 4-17=-715/1890, 5-17=-1414/656, 5-15=-324/842, 7-14=-285/799, 7-12=-1362/606, 8-12=-681/1857

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=912, 10=946.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 64 lb down and 61 lb up at 7-0-0, 64 lb down and 58 lb up at 9-0-12, 64 lb down and 58 lb up at 11-0-12, 64 lb down and 58 lb up at 13-0-12, 64 lb down and 58 lb up at 15-0-12, 64 lb down and 58 lb up at 17-1-4, 64 lb down and 58 lb up at 19-1-4, 64 lb down and 58 lb up at 21-1-4, and 64 lb down and 58 lb up at 23-1-4, and 163 lb down and 176 lb up at 25-2-0 on top chord, and 416 lb down and 215 lb up at 7-0-0, 158 lb down and 78 lb up at 9-0-12, 158 lb down and 78 lb up at 11-0-12, 158 lb down and 78 lb up at 13-0-12, 158 lb down and 78 lb up at 15-0-12, 158 lb down and 78 lb up at 17-1-4, 158 lb down and 78 lb up at 19-1-4, 158 lb down and 78 lb up at 21-1-4, and 158 lb down and 78 lb up at 23-1-4, and 416 lb down and 215 lb up at 25-1-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973369
2584809	T12	Hip Girder	1	1	Job Reference (optional)	

LOAD CASE(S)
Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 4-8=-54, 8-11=-54, 2-10=-20

Concentrated Loads (lb)

Vert: 4=-18(B) 8=-93(B) 17=-416(B) 5=-18(B) 7=-18(B) 12=-416(B) 22=-18(B) 23=-18(B) 24=-18(B) 25=-18(B) 26=-18(B) 27=-18(B) 28=-158(B) 29=-158(B) 30=-158(B) 31=-158(B) 32=-158(B) 33=-158(B) 34=-158(B) 35=-158(B)


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973370
2584809	T13	Hip	1	1		

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021
MiTek Industries, Inc.
Wed Feb 24 09:55:35 2021
Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-9iDk?h1ZmGPnesoeE1DTvtU8pUVy_d4Jx8KPATzhyw6
23-2-0
27-3-6
32-2-0
33-6-0
7-1-0
4-1-6
4-10-10
1-4-0

Scale = 1:57.7




Plate Offsets (X,Y)--		[2:0-1-5,0-1-8], [4:0-3-0,0-2-3], [6:0-3-0,0-2-3], [8:0-1-5,0-1-8]	
LOADING (psf)		SPACING-	CSI.
TCLL	20.0	Plate Grip DOL	TC 0.57
TCDL	7.0	Lumber DOL	BC 0.80
BCLL	0.0 *	Rep Stress Incr	WB 0.28
BCDL	10.0	Code FBC2020/TPI2014	Matrix-MS
		DEFL.	PLATES
		in (loc)	GRIP
		Vert(LL)	MT20
		Vert(CT)	244/190
		Horz(CT)	
			Weight: 173 lb FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-10-3 oc purlins.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3	WEBS	1 Row at midpt 5-14, 5-10

REACTIONS.		(size) 2=0-5-8, 8=0-5-8
		Max Horz 2=-146(LC 10)
		Max Uplift 2=-267(LC 12), 8=-267(LC 13)
		Max Grav 2=1368(LC 2), 8=1368(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	2-3=-1963/378, 3-4=-1813/352, 4-5=-1459/330, 5-6=-1459/330, 6-7=-1813/352, 7-8=-1963/379
BOT CHORD	2-14=-321/1612, 12-14=-292/1868, 10-12=-292/1868, 8-10=-224/1612
WEBS	4-14=-88/746, 5-14=-591/196, 5-12=0/355, 5-10=-591/196, 6-10=-88/746

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=267, 8=267.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:


February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T15	Hip	1	1	T22973372

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:37 2021 Page 1

ID:132pVj5BVg?fJzzugcSEYRy57kM-65LVPN2qItfVtAy0MSFx_IzVSiEOSR_cOSpVELzhyw4



Scale = 1:60.9





Plate Offsets (X,Y)-- [3:0-4-0,0-1-9], [4:0-3-0,0-2-3], [6:0-2-3,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.49	Vert(LL)	-0.13 9-10	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.61	Vert(CT)	-0.21 9-10	>999	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.64	Horz(CT)	0.07 6	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS					Weight: 179 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-9-10 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-11-1 oc bracing.
WEBS 1 Row at midpt 3-9

REACTIONS.

(size) 1=0-5-8, 6=0-5-8
Max Horz 1=184(LC 10)
Max Uplift 1=231(LC 12), 6=231(LC 13)
Max Grav 1=1301(LC 19), 6=1296(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1986/353, 2-3=-1533/312, 3-4=-1195/311, 4-5=-1524/312, 5-6=-1978/353
BOT CHORD 1-12=-336/1693, 10-12=-336/1693, 9-10=-146/1214, 7-9=-212/1593, 6-7=-212/1593
WEBS 2-12=0/266, 2-10=-575/231, 3-10=-92/595, 4-9=-78/554, 5-9=-576/231, 5-7=0/265

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=231, 6=231.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T16	Piggyback Base	1	1	T22973373

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,
8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:38 2021 Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-aHutdj3S3BnMVKXDv9mAXV6gDiZdBuxmd6Y3nozhyw3
25-7-1
6-5-1
32-2-0
6-6-15




Plate Offsets (X,Y)--		[3:0-3-12,0-2-0], [4:0-3-12,0-2-0], [6:0-2-3,Edge]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 20.0	Plate Grip DOL 1.25	TC 0.49	in (loc) l/defl L/d
TCDL 7.0	Lumber DOL 1.25	BC 0.61	Vert(LL) -0.13 9-10 >999 240
BCLL 0.0 *	Rep Stress Incr YES	WB 0.66	Vert(CT) -0.21 9-10 >999 180
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS	Horz(CT) 0.07 6 n/a n/a
			PLATES MT20
			GRIP 244/190
			Weight: 179 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-9-9 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 9-10-15 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 3-9

REACTIONS. (size) 1=0-5-8, 6=Mechanical
Max Horz 1=-186(LC 8)
Max Uplift 1=-230(LC 12), 6=-230(LC 13)
Max Grav 1=1301(LC 19), 6=1296(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1987/352, 2-3=-1529/312, 3-4=-1181/310, 4-5=-1520/312, 5-6=-1978/353
BOT CHORD 1-12=-337/1694, 10-12=-337/1694, 9-10=-144/1202, 7-9=-212/1594, 6-7=-212/1594
WEBS 2-12=0/266, 2-10=-592/235, 3-10=-94/605, 4-9=-81/564, 5-9=-592/236, 5-7=0/265

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=230, 6=230.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021



Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T17	Piggyback Base Girder	1	1	T22973374
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:39 2021 Page 1

ID:I32pVj5BVg?fJzzugcSEYRy57kM-2TSFq344qUvD7U5PTtIP3jeoN5rqrwKYvsmIcJEzhyw2




Plate Offsets (X,Y)--	[3:0-6-4,0-2-4], [4:0-4-4,0-2-4]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.66	Vert(LL)	-0.23 12	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.87	Vert(CT)	-0.40 12-14	>999	180		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.77	Horz(CT)	0.10 9	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS					Weight: 250 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 2-5-7 oc purlins, except end verticals.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 8-1-9 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 5-14, 7-9
REACTIONS.	
(size) 1=0-5-8, 9=Mechanical	
Max Horz 1=180(LC 24)	
Max Uplift 1=248(LC 8), 9=483(LC 9)	
Max Grav 1=1557(LC 2), 9=2192(LC 2)	

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-2462/387, 2-3=-1977/342, 3-4=-1764/380, 4-5=-2183/395, 5-6=-3549/635, 6-7=-4455/825
BOT CHORD	1-17=-404/2024, 15-17=-404/2024, 14-15=-217/1583, 12-14=-507/2959, 11-12=-832/4500, 10-11=-655/3130, 9-10=-655/3130
WEBS	2-17=0/301, 2-15=-620/238, 3-15=-100/597, 3-14=-140/424, 4-14=-133/909, 5-14=-1518/417, 5-12=-236/1442, 6-12=-1987/419, 6-11=-855/226, 7-11=-369/1677, 7-10=-105/840, 7-9=-3670/761

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=248, 9=483.
 - 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 93 lb down and 62 lb up at 32-2-12, and 79 lb down and 63 lb up at 33-1-4, and 79 lb down and 63 lb up at 35-1-4 on top chord, and 668 lb down and 148 lb up at 32-2-12, and 37 lb down and 11 lb up at 33-1-4, and 37 lb down and 11 lb up at 35-1-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973374
2584809	T17	Piggyback Base Girder	1	1	Job Reference (optional)	

- LOAD CASE(S)**
Standard
- 1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25
- Uniform Loads (plf)
- Vert: 1-3=-54, 3-4=-54, 4-6=-54, 6-8=-54, 1-9=-20
- Concentrated Loads (lb)
- Vert: 10=-636(B) 7=-53(B) 20=-30(B) 21=-30(B) 23=-23(B) 24=-23(B)

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T18	Piggyback Base Girder	1	1	T22973375
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc.
Wed Feb 24 09:55:41 2021
Page 1
ID:132pVj5BVg?fJzzugcSEYRy57kM-_sa0Fi5KM6AwMnFoblKt88k49vdJOEVCJ4njN7zhyw0

1-4-0
1-4-0

5-10-0
5-10-0

10-10-0
5-0-0

18-0-0
7-2-0

24-2-0
6-2-0

31-4-0
7-2-0

36-4-4
5-0-4

41-8-0
5-3-12

Scale = 1:75.0




Plate Offsets (X,Y)--		[3:0-4-0,0-1-9], [4:0-6-0,0-2-0], [5:0-4-4,0-2-4], [6:0-6-4,0-2-4], [7:0-6-0,0-2-0]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 20.0	Plate Grip DOL 1.25	TC 0.96	in (loc) l/defl L/d
TCDL 7.0	Lumber DOL 1.25	BC 0.48	Vert(LL) -0.11 12-14 >999 240
BCLL 0.0 *	Rep Stress Incr NO	WB 0.67	Vert(CT) -0.19 12-14 >999 180
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS	Horz(CT) 0.03 10 n/a n/a
		Weight: 288 lb FT = 20%	

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x6 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 5-15, 6-15, 7-14

REACTIONS.	(size) 10=Mechanical, 2=0-3-8, 18=0-5-8
	Max Horz 2=222(LC 27)
	Max Uplift 10=-228(LC 28), 2=-100(LC 8), 18=-415(LC 8)
	Max Grav 10=1157(LC 2), 2=334(LC 19), 18=2179(LC 2)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-210/377, 3-4=-130/786, 4-5=-852/162, 5-6=-633/166, 6-7=-1248/220, 7-8=-1348/254, 8-9=-1347/253, 9-10=-1069/238
BOT CHORD	2-19=-312/208, 18-19=-314/200, 17-18=-531/159, 15-17=-530/161, 14-15=-86/973, 12-14=-366/2066, 11-12=-367/2057
WEBS	3-19=-169/386, 3-18=-931/296, 4-15=-169/1309, 6-15=-636/154, 6-14=-108/847, 7-14=-1247/317, 7-11=-891/143, 8-11=-304/161, 9-11=-305/1642, 4-18=-1368/206

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=228, 2=100, 18=415.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 210 lb down and 141 lb up at 5-10-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)	Standard
1) Dead + Roof Live (balanced):	Lumber Increase=1.25, Plate Increase=1.25
Uniform Loads (plf)	
Vert:	1-3=-54, 3-4=-54, 4-5=-54, 5-6=-54, 6-7=-54, 7-9=-54, 2-10=-20

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973375
2584809	T18	Piggyback Base Girder	1	1	Job Reference (optional)	

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,
8.430 s Feb 12 2021 MiTek Industries, Inc.
Wed Feb 24 09:55:41 2021
Page 2
ID:l32pVj5BVg?fJzzugcSEYRy57kM-_sa0Fi5KM6AwMnFoblKt88k49vdJOEVCJ4njN7zhyw0

LOAD CASE(S)
Standard
Concentrated Loads (lb)
Vert: 19=-186(B)

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T20	Piggyback Base	1	1	T22973377
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021
MiTek Industries, Inc.
Wed Feb 24 09:55:43 2021
Page 1

1-4-0
1-4-0

4-9-5
4-9-5

9-10-0
5-0-11

14-10-0
5-0-0

18-0-0
3-2-0

24-2-0
6-2-0

27-4-0
3-2-0

34-4-4
7-0-4

41-8-0
7-3-12

Scale = 1:75.0




Plate Offsets (X,Y)--		[2:0-1-5,0-1-8], [4:0-3-0,0-2-3], [5:0-5-4,0-2-4], [6:0-6-4,0-2-4], [7:0-4-4,0-2-4], [8:0-4-12,0-2-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.62
TCDL 7.0	Lumber DOL	1.25	BC 0.69
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.94
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS
		DEFL. in (loc) l/defl L/d Vert(LL) -0.17 19-22 >672 240 Vert(CT) -0.35 19-22 >333 180 Horz(CT) 0.04 11 n/a n/a	
		PLATES GRIP MT20 244/190 Weight: 288 lb FT = 20%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 4-5-15 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS	2x4 SP No.3	WEBS	6-0-0 oc bracing: 2-19. 1 Row at midpt 5-19, 6-16, 9-11

REACTIONS.	(size) 11=Mechanical, 2=0-3-8, 19=0-5-8
	Max Horz 2=273(LC 12)
	Max Uplift 11=233(LC 13), 2=-109(LC 24), 19=401(LC 12)
	Max Grav 11=1219(LC 2), 2=171(LC 23), 19=2210(LC 2)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-119/490, 3-4=-168/711, 4-5=-74/541, 5-6=-807/131, 6-7=-965/199, 7-8=-1204/207, 8-9=-1358/217
BOT CHORD	2-19=-361/79, 18-19=-68/378, 16-18=-70/377, 15-16=-106/629, 13-15=-215/1355, 12-13=-197/1092, 11-12=-197/1092
WEBS	3-19=-341/191, 4-19=-591/210, 5-19=-1487/197, 5-16=-84/581, 6-16=-331/96, 6-15=-136/616, 7-15=-45/458, 8-15=-883/205, 9-13=-47/357, 9-12=0/431, 9-11=-1453/261

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 11=233, 2=109, 19=401.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021


Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T21	Piggyback Base	1	1	T22973378

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:45 2021 Page 1
ID:l32pVj5BVg?fJzzugcSEYRy57kM-tdpW569rQKgMrPZZq8OpJ_uuXWz6K_InEilwWuzhyvy

1-4-0
1-4-0
6-1-3
6-1-3
11-10-0
5-8-13
16-10-0
5-0-0
18-0-0
1-2-0
24-2-0
6-2-0
25-4-0
1-2-0
29-10-0
4-6-0
35-6-13
5-8-13
41-8-0
6-1-3

Scale = 1:75.7



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.25	TC 0.42	Vert(LL)	-0.12 13-15	>999	240	MT20	244/190
TCDL 7.0	Lumber DOL 1.25	BC 0.56	Vert(CT)	-0.20 13-15	>999	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.91	Horz(CT)	0.05 11	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MS					Weight: 300 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-11-2 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2x4 SP No.3	WEBS 5-1-3 oc bracing: 19-20.
REACTIONS.	
(size) 11=Mechanical, 2=0-3-8, 20=0-5-8	
Max Horz 2=198(LC 9)	
Max Uplift 11=-239(LC 13), 2=-99(LC 12), 20=-285(LC 12)	
Max Grav 11=1267(LC 2), 2=519(LC 25), 20=1662(LC 2)	

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-510/67, 3-4=-375/111, 4-5=-880/206, 5-6=-1067/259, 6-7=-1027/253, 7-8=-1535/385, 8-9=-1278/304, 9-10=-1541/338, 10-11=-1947/370
BOT CHORD	2-21=-125/447, 20-21=-125/447, 19-20=-1106/283, 17-19=-84/336, 16-17=-126/867, 15-16=-119/1142, 13-15=-65/1217, 12-13=-232/1571, 11-12=-232/1571
WEBS	3-20=-2008/380, 3-19=-191/1675, 4-19=-1017/169, 4-17=-163/1134, 5-17=-730/208, 6-16=-104/520, 7-16=-389/126, 7-15=-292/1023, 8-15=-960/280, 9-13=-88/517, 10-13=-517/206

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 11=239, 20=285.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T22	Hip	1	1	T22973379

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:46 2021 Page 1

ID:132pVj5BVg?fJzzugcSEYRy57kM-LqNviS9TBEOPTY8INrw2rBR0KwHQ3UHxTMUU2Kzhvxx

1-4-0	7-1-3	13-10-0	20-10-0	27-10-0	34-6-13	41-8-0
1-4-0	7-1-3	6-8-13	7-0-0	7-0-0	6-8-13	7-1-3

Scale = 1:74.4




Plate Offsets (X,Y)--		[3:0-4-0,0-3-0], [4:0-4-0,0-1-9], [6:0-4-0,0-1-9], [7:0-4-0,0-3-0], [8:0-2-3,Edge]
LOADING (psf)	SPACING-	2-0-0
TCLL 20.0	Plate Grip DOL	1.25
TCDL 7.0	Lumber DOL	1.25
BCLL 0.0 *	Rep Stress Incr	YES
BCDL 10.0	Code	FBC2020/TPI2014
	CSI.	
	TC	0.55
	BC	0.68
	WB	0.77
	Matrix-MS	
	DEFL.	
	in (loc)	l/defl
	Vert(LL)	-0.13 10-12 >999 240
	Vert(CT)	-0.22 10-12 >999 180
	Horz(CT)	0.05 8 n/a n/a
	PLATES	GRIP
	MT20	244/190
	Weight: 253 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 3-7-1 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2x4 SP No.3	WEBS 6-0-0 oc bracing: 14-15.
	1 Row at midpt 3-15, 4-14, 5-12, 6-12

REACTIONS.	(size) 2=0-3-8, 15=0-5-8, 8=Mechanical
	Max Horz 2=208(LC 9)
	Max Uplift 2=113(LC 12), 15=293(LC 12), 8=264(LC 13)
	Max Grav 2=547(LC 25), 15=1640(LC 2), 8=1300(LC 2)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-515/109, 3-4=-716/198, 4-5=-1097/310, 5-6=-1097/311, 6-7=-1479/368, 7-8=-1963/405
BOT CHORD	2-16=-190/407, 15-16=-187/402, 14-15=-654/210, 12-14=-126/563, 10-12=-79/1153, 9-10=-247/1566, 8-9=-246/1574
WEBS	3-16=-78/259, 3-15=-1872/362, 3-14=-133/1470, 4-14=-673/119, 4-12=-198/954, 5-12=-448/210, 6-10=-102/644, 7-10=-610/243, 7-9=0/287

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCdL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=113, 15=293, 8=264.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973380
2584809	T23	Hip	1	1		

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:47 2021 Page 1

ID:132pVj5BVg?fJzzugcSEYRy57kM-p0xHWoA5xyw44ijxxYRHOP_8SKbao?X4h0E1amzhyvww



Scale = 1:77.3





Plate Offsets (X,Y)-- [2:0-6-0,0-0-4], [5:0-3-0,0-2-3], [7:0-3-0,0-2-3], [10:0-2-3,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.72	Vert(LL)	0.13 17-20	>967	240	MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.81	Vert(CT)	-0.58 13-14	>651	180		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.51	Horz(CT)	0.04 10	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS						
								Weight: 251 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
12-15: 2x4 SP M 31
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-2-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 14-16.
WEBS 1 Row at midpt 3-16, 6-14, 9-13

REACTIONS. (size) 2=0-3-8, 16=0-5-8, 10=Mechanical
Max Horz 2=237(LC 9)
Max Uplift 2=-98(LC 12), 16=-306(LC 12), 10=-257(LC 13)
Max Grav 2=521(LC 25), 16=1719(LC 2), 10=1354(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-437/111, 3-5=-860/229, 5-6=-624/219, 6-7=-1046/340, 7-9=-1368/336,
9-10=-1956/391
BOT CHORD 2-17=-191/350, 16-17=-191/350, 14-16=-536/205, 13-14=-115/892, 11-13=-227/1581,
10-11=-227/1581
WEBS 3-17=-97/382, 3-16=-1904/352, 3-14=-93/1339, 6-14=-650/183, 6-13=-91/446,
7-13=-52/444, 9-13=-761/288, 9-11=0/378

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 16=306, 10=257.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




6904 Parke East Blvd.
Tampa, FL 33610

Job 2584809	Truss T24	Truss Type Common	Qty 4	Ply 1	CHRISMILL HOMES - TODD RES. T22973381
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:48 2021 Page 1
ID:132pVj5BVg?fJzzugcSEYRy57kM-HCVfj8BjIF2xisH8VGyWwcWPhk?IXWEEwgzb6Dzhvv



Scale: 1/4"=1'

Plate Offsets (X,Y)-- [2:0-6-0,0-0-3], [6:0-6-0,0-0-3]									
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.36	Vert(LL)	-0.08 8-10	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.56	Vert(CT)	-0.16 10-13		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.22	Horz(CT)	0.03 6		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS					
								Weight: 113 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-6 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 6=0-3-8
Max Horz 2=-176(LC 10)
Max Uplift 2=-179(LC 12), 6=-179(LC 13)
Max Grav 2=951(LC 2), 6=951(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1256/229, 3-4=-1137/242, 4-5=-1137/242, 5-6=-1256/229
BOT CHORD 2-10=-259/1025, 8-10=-119/671, 6-8=-111/1025
WEBS 4-8=-177/518, 5-8=-299/200, 4-10=-177/518, 3-10=-299/200

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=179, 6=179.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T24G	GABLE	1	1	T22973382

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,
8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:49 2021 Page 1
ID:I32pVj5BVg?fJzzugcSEYRy57kM-IP31xUCLTZAoK0sK3zTITq3Z37OtGsfN9Kj8ffzhyvu

-1-4-0
1-4-0
5-1-0
5-1-0
11-0-0
5-11-0
16-11-0
5-11-0
22-0-0
5-1-0
23-4-0
1-4-0

4x6 ||

Scale = 1:49.3




Plate Offsets (X,Y)--		[2:0-3-5,0-3-0], [5:0-2-0,0-0-0], [8:0-3-5,0-3-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.39
TCDL 7.0	Lumber DOL	1.25	BC 0.38
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.66
BCDL 10.0	Code	FBC2020/TPI2014	Matrix-MS
			DEFL.
			in (loc)
			Vert(LL) -0.06 10-33 >999 240
			Vert(CT) -0.12 10-33 >890 180
			Horz(CT) 0.00 8 n/a n/a
			PLATES
			MT20
			GRIP
			244/190
			Weight: 168 lb FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

REACTIONS. All bearings 13-3-8 except (jt=length) 8=0-3-8, 11=0-3-8, 11=0-3-8.

(lb) - Max Horz 2=-169(LC 10)

Max Uplift All uplift 100 lb or less at joint(s) 2, 12, 11 except 8=-131(LC 13), 15=-211(LC 12)

Max Grav All reactions 250 lb or less at joint(s) 12, 14, 16, 17, 11, 11, 2 except 2=265(LC 23), 8=603(LC 20), 15=801(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 4-5=-29/250, 5-6=-467/144, 6-8=-604/143

BOT CHORD 8-10=-46/501

WEBS 5-10=-96/462, 6-10=-352/203, 5-15=-564/87, 4-15=-300/204

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 12, 11, 2 except (jt=lb) 8=131, 15=211.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T25	Common Girder	1	2	T22973383




Plate Offsets (X,Y)-- [1:Edge,0-3-0], [7:Edge,0-3-0], [8:0-5-12,0-1-8], [9:0-3-8,0-4-8], [10:0-6-0,0-6-0], [11:0-3-8,0-4-8], [12:0-5-12,0-1-8]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	20.0	Plate Grip DOL	1.25	TC	0.59	Vert(LL)	-0.16	9-10	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.42	Vert(CT)	-0.28	9-10	>948	180		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.85	Horz(CT)	0.06	7	n/a	n/a		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS							Weight: 333 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 3-3-3 oc purlins.
BOT CHORD	2x8 SP 2400F 2.0E	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3 *Except*		
	4-10: 2x4 SP No.2		
REACTIONS.			
	(size) 1=0-5-8, 7=0-5-8		
	Max Horz 1=157(LC 26)		
	Max Uplift 1=1374(LC 8), 7=1443(LC 9)		
	Max Grav 1=6495(LC 2), 7=6941(LC 2)		

FORCES.		(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	1-2=-11254/2381, 2-3=-9014/1905, 3-4=-7024/1525, 4-5=-7024/1526, 5-6=-9083/1905, 6-7=-11276/2343		
BOT CHORD	1-12=-2025/9337, 11-12=-2025/9337, 10-11=-1553/7473, 9-10=-1497/7528, 8-9=-1889/9364, 7-8=-1889/9364		
WEBS	4-10=-1610/7560, 5-10=-3025/721, 5-9=-732/3521, 6-9=-2362/569, 6-8=-511/2536, 3-10=-2928/720, 3-11=-730/3397, 2-11=-2397/607, 2-12=-559/2602		

NOTES-			
1)	2-ply truss to be connected together with 10d (0.131"x3") nails as follows: Top chords connected as follows: 2x4 - 1 row at 0-7-0 oc. Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-8-0 oc. Webs connected as follows: 2x4 - 1 row at 0-9-0 oc, Except member 2-12 2x4 - 1 row at 0-4-0 oc.		
2)	All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.		
3)	Unbalanced roof live loads have been considered for this design.		
4)	Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60		
5)	Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.		
6)	This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.		
7)	* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.		
8)	Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=1374, 7=1443.		
9)	Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 2172 lb down and 503 lb up at 3-10-12, 1137 lb down and 248 lb up at 5-10-12, 1125 lb down and 251 lb up at 7-10-12, 1199 lb down and 253 lb up at 9-10-12, 1247 lb down and 259 lb up at 11-10-12, 1280 lb down and 284 lb up at 13-10-12, 1310 lb down and 277 lb up at 15-10-12, and 1278 lb down and 282 lb up at 17-10-12, and 1278 lb down and 282 lb up at 19-10-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.		

Continued on page 2			
LOAD CASE(S) Standard			
<div> <div></div> <div>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</div> </div> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see</p> <p>Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>		<div> <div></div> <div>ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component</div> </div>	
		<div> <div></div> <div> <div> <div></div> <div>MiTek</div> </div> <div>6904 Parke East Blvd. Tampa, FL 36610</div> </div> </div>	

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973383
2584809	T25	Common Girder	1	2	Job Reference (optional)	

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)

Vert: 1-4=-54, 4-7=-54, 1-7=-20


Concentrated Loads (lb)

Vert: 8=-1164(F) 11=-1044(F) 17=-2043(F) 18=-1049(F) 19=-1049(F) 20=-1145(F) 21=-1159(F) 22=-1148(F) 23=-1164(F)


Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973384
2584809	T26G	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Jacksonville, FL),
Jacksonville, FL - 32244,
8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:52 2021 Page 1

ID:l32pVj5BVg?fJzzugcSEYRy57kM-A_IaZWEEuYMBTbv61S5Sh76LSoTMhprlxoF_zhyvr



Scale = 1:22.4



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	1.25	TC	0.21	Vert(LL)	-0.01	8-15	>999	240	MT20	244/190	
TCDL	7.0	Lumber DOL	1.25	BC	0.17	Vert(CT)	-0.01	8-15	>999	180			
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.07	Horz(CT)	0.00	6	n/a	n/a			
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS							Weight: 50 lb	FT = 20%	

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 6=0-3-8
Max Horz 2=-76(LC 10)
Max Uplift 2=-93(LC 12), 6=-93(LC 13)
Max Grav 2=402(LC 1), 6=402(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-4=-347/70, 4-6=-347/70
BOT CHORD 2-8=-48/268, 6-8=-48/268

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 6.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Job 2584809	Truss T27	Truss Type Common	Qty 1	Ply 1	CHRISMILL HOMES - TODD RES. T22973385
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:53 2021 Page 1
ID:132pVj5BVg?fJzzugcSEYRy57kM-eAlYmrFsXogDodA5IpYhdgEA9leOCoeZ4yhMoQzhvq




Plate Offsets (X,Y)--		[4:0-2-3,Edge]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 20.0	Plate Grip DOL	1.25	TC 0.77
TCDL 7.0	Lumber DOL	1.25	BC 0.79
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.18
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MS
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.16 6-9 >999 240
			Vert(CT) -0.26 6-9 >744 180
			Horz(CT) 0.01 2 n/a n/a
			PLATES GRIP
			MT20 244/190
			Weight: 65 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-7-9 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-5-8, 4=0-5-8
Max Horz 2=133(LC 10)
Max Uplift 2=138(LC 12), 4=138(LC 13)
Max Grav 2=760(LC 19), 4=760(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-817/148, 3-4=-816/148
BOT CHORD 2-6=-44/654, 4-6=-44/654
WEBS 3-6=0/462

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=138, 4=138.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



6904 Parke East Blvd.
Tampa, FL 36610


Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T27G	Common Supported Gable	1	1	T22973386
Job Reference (optional)					

Builders FirstSource (Jacksonville, FL),

Jacksonville, FL - 32244,

8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:54 2021 Page 1

ID:132pVj5BVg?fJzzugcSEYRy57kM-6Msw_BGUI5o4QnlHrX3wAtmVH8ARxHR6lcQvKszhyvp



Scale = 1:33.2




Plate Offsets (X,Y)--		[2:0-3-8,Edge], [12:0-3-8,Edge]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d		PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.25	TC 0.10	Vert(LL)	-0.00	13	n/r	120		MT20	244/190
TCDL 7.0	Lumber DOL	1.25	BC 0.03	Vert(CT)	-0.01	13	n/r	120			
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	12	n/a	n/a			
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S							Weight: 92 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 16-0-0.
(lb) - Max Horz 2=126(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 2, 12, 18, 19, 20, 16, 15, 14
Max Grav All reactions 250 lb or less at joint(s) 2, 12, 17, 18, 19, 20, 16, 15, 14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 12, 18, 19, 20, 16, 15, 14.

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.
2584809	T28	Common Girder	1	2	T22973387

Builders FirstSource (Jacksonville, FL), Jacksonville, FL - 32244, 8.430 s Feb 12 2021 MiTek Industries, Inc. Wed Feb 24 09:55:56 2021 Page 1
ID:I32pVj5BVg?fiJzzugcSEYRy57kM-2L_hPtHkqj2of5vgzx5OFIrmtynoP2xPmwv0Olzhvyn




Plate Offsets (X,Y)-- [2:0-4-0,0-1-9], [6:0-4-0,0-1-9], [7:0-5-8,0-1-8], [8:0-6-0,0-5-12], [9:0-5-8,0-1-8]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	20.0	Plate Grip DOL	1.25	TC	0.42	Vert(LL)	-0.08	7-8	>999	240	MT20	244/190
TCDL	7.0	Lumber DOL	1.25	BC	0.36	Vert(CT)	-0.14	7-8	>999	180		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.63	Horz(CT)	0.03	6	n/a	n/a		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MS							Weight: 215 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-1-6 oc purlins.
BOT CHORD 2x8 SP 2400F 2.0E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3 *Except*	
4-8: 2x4 SP No.2	

REACTIONS. (size) 6=0-5-8, 2=0-5-8
Max Horz 2=127(LC 24)
Max Uplift 6=1376(LC 9), 2=947(LC 8)
Max Grav 6=6183(LC 2), 2=3357(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-5743/1642, 3-4=-5196/1468, 4-5=-5210/1469, 5-6=-8010/1870
BOT CHORD 2-9=-1379/4731, 8-9=-1379/4731, 7-8=-1504/6653, 6-7=-1504/6653
WEBS 4-8=-1544/5500, 5-8=-3057/546, 5-7=-460/3283, 3-8=-555/301, 3-9=-196/456

- NOTES-
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-4-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=101mph; TCDL=4.2psf; BCDL=3.0psf; h=18ft; Cat. II; Exp B; Encl., GCpi=0.18; MWFRS (envelope) gable end zone; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=1376, 2=947.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 2491 lb down and 1055 lb up at 7-0-12, 1272 lb down and 199 lb up at 9-0-12, 1641 lb down and 252 lb up at 11-0-12, and 1631 lb down and 321 lb up at 13-0-12, and 1620 lb down and 316 lb up at 15-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

This item has been electronically signed and sealed by Velez, Joaquin, PE using a Digital Signature. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.
Joaquin Velez PE No.68182
MiTek USA, Inc. FL Cert 6634
6904 Parke East Blvd. Tampa FL 33610
Date:

February 25,2021

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



6904 Parke East Blvd.
Tampa, FL 36610

Job	Truss	Truss Type	Qty	Ply	CHRISMILL HOMES - TODD RES.	T22973387
2584809	T28	Common Girder	1	2	Job Reference (optional)	

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.25, Plate Increase=1.25

Uniform Loads (plf)


Vert: 1-4=-54, 4-6=-54, 2-6=-20

Concentrated Loads (lb)


Vert: 11=-1468(F) 14=-2491(F) 15=-1152(F) 16=-1467(F) 17=-1467(F)

Symbols

PLATE LOCATION AND ORIENTATION



0-¹/₁₆"



For 4 x 2 orientation, locate plates 0- ¹/₁₆" from outside edge of truss.

—
—
This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MiTek 20/20** software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or L bracing if indicated.


BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:
ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MiTek® All Rights Reserved



MiTek Engineering Reference Sheet: MIL-7473 rev. 5/19/2020

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative for l bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.