

Builder/Contractor Responsibilities

Drawing Validity – These drawings, supporting structural calculations and design certification are based on the order documents as of the date of these drawings. These documents describe the material supplied by the manufacturer as of the date of these drawings. Any changes to the order documents after the date on these drawings may void these drawings, supporting structural calculations and design certification. The Builder/Contractor is responsible for notifying the building authority of all changes to the order documents which result in changes to the drawings, supporting structural calculations and design certification.

Builder Acceptance of Drawings – Approval of the manufacturer's drawings and design data affirms that the manufacturer has correctly interpreted and applied the requirements of the order documents and constitutes Builder/Contractor acceptance of the manufacturer's interpretations of the order documents and standard product specifications, including its design, fabrication and quality criteria standards and tolerances. (AISC code of standard practice Sept 86 Section 4.2.1) (Mar 05 Section 4.4.1)

Code Official Approval – It is the responsibility of the Builder/Contractor to ensure that all project plans and specifications comply with the applicable requirements of any governing building authority. The Builder/Contractor is responsible for securing all required approvals and permits from the appropriate agency as required.

Builder is responsible for State, Federal and OSHA safety compliance – The Builder/Contractor is responsible for applying and observing all pertinent safety rules and regulations and OSHA standards as applicable.

Building Erection – The Builder/Contractor is responsible for all erection of the steel and associated work in compliance with the Metal Building Manufacturers drawings. Temporary supports, such as temporary guys, braces, false work or other elements required for erection will be determined, furnished and installed by the erector. (AISC Code of Standard Practice Sept 86 Section 7.9.1) (Mar 05 Section 7.10.3)

Discrepancies – Where discrepancies exist between the Metal Building plans and plans for other trades, the Metal Building plans will govern. (AISC Code of Standard Practice Sept 86 Section 3.3) (Mar 05 Section 3.3)

Materials by Others – All interface and compatibility of any materials not furnished by the manufacturer are the responsibility of and to be coordinated by the Builder/Contractor or A/E firm. Unless specific design criteria concerning any interface between materials if furnished as a part of the order documents, the manufacturers assumptions will govern.

Modification of the Metal Building from Plans – The Metal Building supplied by the manufacturer has been designed according to the Building Code and specifications and the loads shown on this drawing. Modification of the building configuration, such as removing wall panels or braces, from that shown on these plans could affect the structural integrity of the building. The Metal Building Manufacturer or a Licensed Structural Engineer should be consulted prior to making any changes to the building configuration shown on these drawings. The Metal Building Manufacturer will assume no responsibility for any loads applied to the building not indicated on these drawings.

Foundation Design – The Metal Building Manufacturer is not responsible for the design, materials and workmanship of the foundation. Anchor rod plans prepared by the manufacturer are intended to show only location, diameter and projection of the anchor rods required to attach the Metal Building System to the foundation. It is the responsibility of the end customer to ensure that adequate provisions are made for specifying rod embedment, bearing values, tie rods and or other associated items embedded in the concrete foundation, as well as foundation design for the loads imposed by the Metal Building System, other imposed loads, and the bearing capacity of the soil and other conditions of the building site. (MBMA 06 Sections 3.2.2 and A3)

Project Notes

Material properties of steel bar, plate, and sheet used in the fabrication of built-up structural framing members conform to ASTM A529, ASTM A572, ASTM A1011 SS, or ASTM A1011 HSLAS with a minimum yield point of 50 ksi. Material properties of hot rolled structural shapes conform to ASTM A992, ASTM A529, or ASTM A572 with a minimum specified yield point of 50 ksi. Hot rolled angles, or other than flange braces, conform to ASTM 36 minimum. Hollow structural shaped conform to ASTM A500 grade b, minimum yield point is 42 ksi for round HSS and 46 ksi for rectangular HSS. Material properties of cold form light gage steel members conform to the requirements of ASTM A1011 SS Grade 55 or ASTM A1011 HSLAS Class 1 Grade 55, with a minimum yield point of 35 ksi.

The manufacturer does not assume any responsibility for the erection nor field supervision of the structure and or any special inspections that may be required by the local building authority during erection (including inspection of the high strength bolts or field welds) as required during erection. The coordination and the costs associated for setting up and Special inspections are the responsibility of the Erector, Owner, Architect, or Engineer of Record.

Design is based upon the more severe loading of either the roof snow load or the roof live load.

Loads, as noted, are given within order documents and are applied in general accordance with the applicable provisions of the model code and/or specification indicated. Neither the manufacturer nor the certifying engineer declares or attests that the loads as designated are proper for the local provisions that may apply or for site specific parameters. The manufacturer's Engineer's certification is limited to design loads supplied by an Architect and/or engineer of record for the overall construction project.

This project is designed using manufacture's standard serviceability standards. Generally this means that all stresses and deflections are within typical performance limits for normal occupancy and standard metal building products. If special requirements for deflections and vibrations must be adhered to, then they must be clearly stated in the contract documents.

This metal building system is designed as enclosed. All exterior components (i.e. doors, windows, vents, etc.) must be designed to withstand the specified wind loading for the design of components and cladding in accordance with the specified building code. Doors are to be closed when a maximum of 50% of design wind velocity is reached.

Using standard 5x5 eave gutter with 4 x 5 downspouts, the roof drainage system has been designed using the method outlined in the MBMA Metal Building Systems Manual. Downspout locations have not been located on these drawings. The downspouts are to be placed on the building sidewalls at a spacing not to exceed 23 feet with the first downspout from both ends of the gutter run within 20 feet of the end. Downspout spacing that does not exceed the maximum spacing will be in compliance with the building code. The gutter and downspout system as provided by the manufacturer is designed to accommodate 10 in./hr rainfall intensity.

The rigid frame at lines 1&7 are designed as a non-expandable rigid frame. Corresponding frame reactions are calculated based upon actual tributary area.

Roof and wall panels have been designed in accordance with section 2222.4 of the Florida Building Code, Sixth Edition (2017). Product approval numbers for the State of Florida, Department of Community Affairs per Product Rule 9B-72:

FLORIDA APPROVAL #

| |
|----------------|
| FL11868.1 |
| PBR ROOF PANEL |
| FL11917.5 |
| PBR WALL PANEL |

Design Loading

This structure is designed utilizing the loads indicated and applied as required by:

FBC 2017(6TH EDITION)

THE BUILDER IS TO CONFIRM THAT THESE LOADS COMPLY WITH THE REQUIREMENTS OF THE LOCAL BUILDING DEPARTMENT.

| | |
|---------------------------------|-----------|
| ROOF DEAD LOAD | 1.760 PSF |
| SUPERIMPOSED COLLATERAL (L/HTS) | 3.5 PSF |

| | |
|----------------|-----------------------|
| ROOF LIVE LOAD | 20.00 PSF (REDUCIBLE) |
|----------------|-----------------------|

| | |
|---------------|-------------|
| RISK CATEGORY | II – Normal |
|---------------|-------------|

SNOW LOAD

| | |
|-----------------------|------------|
| GROUND SNOW LOAD (Pg) | 0.0000 PSF |
|-----------------------|------------|

| | |
|----------------------------------|--------|
| SNOW LOAD IMPORTANCE FACTOR (Is) | 1.0000 |
|----------------------------------|--------|

| | |
|--------------------------|-------|
| FLAT ROOF SNOW LOAD (Pp) | 0 PSF |
|--------------------------|-------|

| | |
|---------------------------|-----|
| SNOW EXPOSURE FACTOR (Ce) | 1.0 |
|---------------------------|-----|

| | |
|---------------------|------|
| THERMAL FACTOR (Ct) | 1.00 |
|---------------------|------|

WIND LOAD

| | |
|---------------------|---------|
| ULTIMATE WIND SPEED | 121 MPH |
|---------------------|---------|

| | |
|--------------------------|-----------------------------|
| NOMINAL WIND SPEED(Vwst) | 94 MPH/HC SECTION 1609.3.1) |
|--------------------------|-----------------------------|

| | |
|---------------------------|--------|
| SERVICEABILITY WIND SPEED | 76 MPH |
|---------------------------|--------|

| | |
|------------------------|---|
| WIND EXPOSURE CATEGORY | B |
|------------------------|---|

| | |
|----------------------|-----|
| TOPOGRAPHICAL FACTOR | 1.0 |
|----------------------|-----|

| | |
|-------------------------------------|--------------|
| INTERNAL PRESSURE COEFFICIENT (GcP) | 0.18 / -0.18 |
|-------------------------------------|--------------|

| | |
|---|--|
| ZONE 4, COMPONENT WIND LOAD < 10ft ² | |
|---|--|

| | |
|---|--|
| 24.085 PSF PRESSURE -26.092 PSF SUCTION | |
|---|--|

| | |
|---|--|
| ZONE 5, COMPONENT WIND LOAD < 10ft ² | |
|---|--|

| | |
|---|--|
| 24.085 PSF PRESSURE -32.053 PSF SUCTION | |
|---|--|

ZONES PER ASCE 7-10: FG, 30.4-1

ZONES PRESSURES SHOWN ARE UN-FACTORED

RAIN INTENSITY

5-MINUTE DURATION, 5-YEAR

RECURRENT (11)

10.0000 IN/HOUR



THIS CERTIFICATION COVERS PARTS MANUFACTURED AND DELIVERED BY THE MANUFACTURER ONLY AND EXCLUDES PARTS SUCH AS DOORS, WINDOWS, FOUNDATION DESIGN AND ERECTION OF THE BUILDING. THESE DRAWINGS AND THE METAL BUILDING SYSTEM THEY REPRESENT ARE THE PRODUCT OF AN AFFILIATE OF NCI GROUP, INC. – 10943 N. SAM HOUSTON PARKWAY W. HOUSTON, TX 77064. THE PROFESSIONAL ENGINEER WHOSE SEAL APPEARS HEREON IS EMPLOYED BY AN AFFILIATE OF NCI GROUP, INC. AND IS NOT THE ENGINEER-OF-RECORD FOR THE OVERALL PROJECT. THE ENGINEER WHOSE SEAL APPEARS HEREON IS AN EMPLOYEE FOR THE MANUFACTURER FOR THE MATERIALS DESCRIBED HEREIN. SAID SEAL OR CERTIFICATION IS LIMITED TO THE PRODUCTS DESIGNED AND MANUFACTURED BY MANUFACTURER ONLY. THE UNDERSIGNED ENGINEER IS NOT THE OVERALL ENGINEER OF RECORD FOR THIS PROJECT.

ENGINEERING SEAL

FOR QUESTIONS OR ASSISTANCE CONCERNING ERECTION CALL:
800-556-3726
MONDAY – FRIDAY 7:30AM TO 5:00PM

FOR ERECTOR INSTALLATION
FINAL DRAWINGS FOR CONSTRUCTION.

FOR CONSTRUCTION PERMIT
THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR ERECTOR INSTALLATION" CAN BE CONSIDERED AS COMPLETE.

Drawing Status

| PAGE | DESCRIPTION |
|---------|-----------------------|
| C1 | COVER SHEET |
| F1 | ANCHOR BOLT PLAN |
| F2 | ANCHOR BOLT REACTIONS |
| F3 | ANCHOR BOLT DETAILS |
| E1 | ROOF FRAMING PLAN |
| E2 | ROOF SHEETING PLAN |
| E3 | FRONT SIDEWALL |
| E4 | BACK SIDEWALL |
| E5 | LEFT ENDWALL |
| E6 | RIGHT ENDWALL |
| E7-E12 | FRAME CROSS SECTION |
| E13-E14 | WIND BENT ELEVATION |
| DET1-9 | STANDARD DETAILS |
| R1-R3 | INSTALLATION SHEETS |

FOR APPROVAL
THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR ERECTOR INSTALLATION" CAN BE CONSIDERED AS COMPLETE.

BUILDING SIZE: 95'-0" x 125'-0" x 22'-0"

1.0.12

MESCO Building Solutions

5244 Bear Creek Court
Irving, TX 75061
Voice 214-687-9999
Fox 214-687-9737



PROJECT: TRUCK STOP 75

CUSTOMER: SIMQUE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

DATE: 12/ 6/19

SCALE: N.T.S.

PHASE: 1

BUILDING ID: A

JOB NUMBER: 17-B-46005

SHEET NUMBER: C1


ISSUE: 0

Dec 13, 2019

Drawing has been digitally signed.

☐ Dia = 5/8"

☒ Dia = 3/4"



NOTE: ALL BASE PLATES @ 100.0' (U.N.)
ASSUMED FINISH FLOOR @ 100.0' (U.N.)

| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|----------|--------------------------|-----|------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |



MESCO Building Solutions

5244 Bear Creek Court Irving, TX 75061
Voice 214-687-9999 Fax 214-687-9737

| | |
|-----------|----------------------|
| PROJECT: | TRUCK STOP 75 |
| CUSTOMER: | SIMQUE CONSTRUCTION |
| | OWNER: TRUCK STOP 75 |

Dec 13, 2019

Drawing has been digitally signed.



GENERAL NOTES

1. THE REACTIONS PROVIDED ARE BASED ON THE ORDER DOCUMENTS AT THE TIME OF MAILING. ANY CHANGES TO BUILDING LOADS OR DIMENSIONS MAY CHANGE THE REACTIONS. THE REACTIONS WILL BE SUPERSEDED AND VOIDED BY ANY FUTURE MAILING.
2. REACTIONS ARE PROVIDED AS UN-FACTORED FOR EACH LOAD GROUP APPLIED TO THE COLUMN. THE FOUNDATION ENGINEER WILL APPLY THE APPROPRIATE LOAD FACTORS AND COMBINE THE REACTIONS IN ACCORDANCE WITH THE BUILDING CODE AND DESIGN SPECIFICATIONS TO DETERMINE BEARING PRESSURES AND CONCRETE DESIGN. THE FACTORS APPLIED TO LOAD GROUPS FOR THE STEEL COLUMN DESIGN MAY BE DIFFERENT THAN THE FACTORS USED IN THE FOUNDATION DESIGN.
3. THE MANUFACTURER DOES NOT PROVIDE MAXIMUM LOAD REACTIONS. ENGINEER, THE END USER SHOULD CONSULT THE REACTIONS PROVIDED BY THE MANUFACTURER OF THE FOUNDATION TO DETERMINE THE APPLICABLE LOAD COMBINATIONS FOR HIS/HER DESIGN PROCEDURES AND ALLOW FOR AN ECONOMIC FOUNDATION DESIGN.
4. THE METAL BUILDING MANUFACTURER IS RESPONSIBLE FOR THE DESIGN OF THE ANCHOR BOLT DIAMETER ONLY TO PERMIT THE TRANSFER OF FORCES BETWEEN THE BASE PLATE AND THE ANCHOR BOLT IN SHEAR, BEARING AND TENSION, BUT IS NOT RESPONSIBLE FOR THE ANCHOR BOLT EMBEDMENT FOR TRANSFER OF FORCES TO THE FOUNDATION. THE METAL BUILDING MANUFACTURER DOES NOT DESIGN AND IS NOT RESPONSIBLE FOR THE DESIGN, MATERIAL AND CONSTRUCTION OF THE FOUNDATION EMBEDMENTS. THE END USER CUSTOMER SHOULD ASSURE HIMSELF THAT ADEQUATE PROVISIONS ARE MADE IN THE FOUNDATION DESIGN FOR LOADS IMPOSED BY COLUMN REACTIONS OF THE BUILDING, OTHER IMPOSED LOADS, AND BEARING CAPACITY OF THE SOIL AND OTHER CONDITIONS OF THE BUILDING SITE.
5. IT IS RECOMMENDED THAT THE ANCHORAGE AND FOUNDATION OF THE BUILDING BE DESIGNED BY A LICENSED PROFESSIONAL ENGINEER EXPERIENCED IN THE DESIGN OF SUCH STRUCTURES. (SECTION A3 MBMA 2006 METAL BUILDING SYSTEMS MANUAL.)
6. (UNLESS NOTED)
7. BOTTOM OF ALL BASE PLATES ARE AT THE SAME ELEVATION.
8. ANCHOR RODS ARE ASTM F1554 GRADE 36 MATERIAL UNLESS NOTED OTHERWISE.

BUILDING BRACING REACTIONS

| Well | | Col | | Reactions in plane of wall | | Panel Shear | | Note |
|------|------|-----|------|----------------------------|---------|-------------|------|------|
| Loc | Line | Loc | Line | Wind | Seismic | Wind | Seis | |
| F_EW | A | 1 | 4.5 | | | | | (h) |
| F_SW | A | 5 | | | | | | (h) |
| R_EW | I | 7 | 4.5 | | | | | (h) |
| B_SW | I | 4 | | | | | | (o) |

(o) Wind bent in bay
(h) Rigid frame at endwall

WIND BENT REACTIONS



| Well | | Col | | Reactions | | Base Plate | | Thick |
|------|------|-----|------|-----------|------------|------------|-------|--------|
| Loc | Line | Loc | Line | Wind(k) | Seismic(k) | Qty | Do | |
| F_SW | A | 4 | 4.8 | 11.0 | 0.8 | 4 | 0.750 | 14,500 |
| F_SW | A | 5 | 4.8 | 11.0 | 0.8 | 4 | 0.750 | 14,500 |
| B_SW | I | 4 | 4.8 | 11.0 | 0.8 | 4 | 0.750 | 14,500 |
| B_SW | I | 4 | 4.8 | 11.0 | 0.8 | 4 | 0.750 | 14,500 |

RIGID FRAME:

BASIC COLUMN REACTIONS (k)

| Frame Column | | Dead | | Collateral | | Live | | Wind Left | | Wind Right | | Wind | |
|--------------|------|-------|------|------------|------|-------|------|-----------|-------|------------|-------|-------|-------|
| Line | Line | Horiz | Vert | Horiz | Vert | Horiz | Vert | Horiz | Vert | Horiz | Vert | Press | Suct |
| 1 | A | 1.3 | 2.5 | 1.2 | 1.8 | 4.1 | 6.0 | -9.6 | -12.9 | -4.8 | -8.8 | -7.8 | -8.8 |
| 2 | A | -1.3 | 2.5 | -1.2 | 1.8 | -4.1 | 6.0 | 9.6 | -12.9 | 4.8 | -8.8 | -3.0 | -8.8 |
| 3 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -14.5 | -12.3 | -13.0 |
| 4 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -14.5 | -4.6 | -8.8 |
| 5 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -11.2 | -11.2 |
| 6 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -3.3 | -5.4 |
| 7 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -12.0 | -11.2 |
| 8 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -10.6 | -10.0 |
| 9 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -7.8 | -8.8 |
| 10 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.0 | -2.0 |
| 11 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 12 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 13 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 14 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 15 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 16 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 17 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 18 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 19 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 20 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 21 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 22 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 23 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 24 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 25 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 26 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 27 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 28 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 29 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 30 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 31 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 32 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 33 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 34 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 35 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 36 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 37 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 38 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 39 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 40 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 41 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 42 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 43 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 44 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 45 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 46 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 47 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 48 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 49 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 50 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 51 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 52 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 53 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 54 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 55 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 56 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 57 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 58 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 59 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 60 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 61 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 62 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 63 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 64 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 65 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 66 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 67 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 68 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 69 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 70 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 71 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 72 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 73 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 74 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 75 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 76 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 77 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 78 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 79 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 80 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 81 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 82 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 83 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 84 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 85 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 86 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 87 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 88 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 89 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 90 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 91 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 92 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 93 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 94 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 95 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 96 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |
| 97 | A | 2.0 | 3.5 | 2.4 | 3.3 | 8.3 | 11.4 | -16.0 | -20.7 | -8.3 | -12.3 | -2.5 | 2.7 |
| 98 | A | -2.0 | 3.5 | -2.4 | 3.3 | -8.3 | 11.4 | 16.0 | -20.7 | 8.3 | -12.3 | -2.5 | 2.7 |
| 99 | A | 2.2 | 3.8 | 2.7 | 3.8 | 9.3 | 12.8 | -15.7 | -19.8 | -9.3 | -12.8 | -2.5 | 2.7 |
| 100 | A | -2.2 | 3.8 | -2.7 | 3.8 | -9.3 | 12.8 | 15.7 | -19.8 | 9.3 | -12.8 | -2.5 | 2.7 |

[illegible][illegible]

| | | | | | |
|---|---------------------|---|---------------|--|------------|
|  | | MESCO Building Solutions | |  | |
| MESCO Building Solutions | | 5244 Bear Creek Court Irving, TX 75061 Voice 214-687-9999 Fax 214-687-9737 | | [Signature] HARBOLD S. MOSCOW PROFESSIONAL ENGINEER | |
| PROJECT: | TRUCK STOP 75 | OWNER: | TRUCK STOP 75 | | |
| CUSTOMER: | SIMQUE CONSTRUCTION | | | | |
| LOCATION: | LAKE CITY, FL 32024 | | | | |
| CAD | DATE | SCALE | PHASE | BUILDING ID | JOB NUMBER |
| | 12/ 6/19 | N.T.S. | 1 | A | 17-B-46005 |
| | | | | SHEET NUMBER | ISSUED |
| | | | | E2 | 0 |


RIGID FRAME ONLY!
WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL
RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE.

| BOLT TABLE | | FRAME LINE 1 | |
|-------------|------|--------------|------|
| LOCATION | QUAN | TYPE | DIA |
| Columns/Ref | 2 | A325 | 1/2" |


| MEMBER TABLE | | FRAME LINE 1 | |
|--------------|---------|--------------|--|
| MARK | PART | LENGTH | |
| EC-1 | WBX18 | 21'-2 11/16" | |
| EC-2 | WBX24 | 22'-5 1/2" | |
| DI-1 | 8F25C16 | 10'-8" | |
| GH06-1 | GH06 | 15'-0" | |
| G-1 | 8X25Z14 | 20'-1" | |
| G-2 | 8X25Z16 | 19'-9 1/2" | |
| G-3 | 8X25Z16 | 21'-11 1/2" | |
| G-4 | 8X25Z16 | 3'-6 1/2" | |
| G-5 | 8X25Z14 | 20'-1" | |
| G-6 | 8X25Z16 | 19'-9 1/2" | |

| CONNECTION PLATES | | FRAME LINE 1 | |
|-------------------|-----------|--------------|--|
| ID | MARK/PART | | |
| 1 | SC-484 | | |

| FLANGE BRACE TABLE | | | |
|--------------------|--------|----------|-----------|
| FRAME LINE 1 | | | |
| ▽ ID | MARK | PART | LENGTH |
| 1 | FB29.3 | L2X2X14G | 2'-5 1/4" |



ENDWALL FRAMING: FRAME LINE 1



ENDWALL SHEETING & TRIM: FRAME LINE 1

PANELS: 26 Gauge PBR - Ash Gray

| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|----------|--------------------------|-----|------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |



MESCO Building Solutions

5244 Bear Creek Court Irving, TX 75061
Voice 214-687-9999 Fax 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SIMQUE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024



OWNER: TRUCK STOP 75

- GENERAL NOTES:
1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
 4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

SECTION-X

Dec 13, 2019

Drawing has been digitally signed.




RIGID FRAME ONLY!
WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL
RAFTER CONNECTION. USE ONE WASHER ON SLOTTED SIDE.

| BOLT TABLE | | | | |
|--------------|--|------|------|--------|
| FRAME LINE 7 | | QUAN | TYPE | DIA |
| LOCATION | | 2 | A325 | 1/2" |
| Columns/Raft | | | | 1 1/4" |


| MEMBER TABLE | | | |
|--------------|---------|-------------|--|
| FRAME LINE 7 | | | |
| MARK | PART | LENGTH | |
| EC-3 | WBX18 | 21'-7 7/16" | |
| EC-4 | WBX18 | 22'-8 1/2" | |
| G-7 | 8X25216 | 24'-6 1/2" | |
| G-8 | 8X25216 | 26'-8 1/2" | |
| G-9 | 8X25216 | 24'-6 1/2" | |

| FLANGE BRACE TABLE | | | |
|--------------------|--------|----------|-----------|
| FRAME LINE 7 | | | |
| ▽ ID | MARK | PART | LENGTH |
| 1 | FB29.3 | 12X2X14G | 2'-5 1/4" |

| CONNECTION PLATES | | |
|-------------------|-----------|--|
| FRAME LINE 7 | | |
| □ ID | MARK/PART | |
| 1 | SC-484 | |



ENDWALL FRAMING: FRAME LINE 7




7'-10" OPEN FOR MASONRY WALL BY OTHERS

ENDWALL SHEETING & TRIM: FRAME LINE 7

PANELS: 26 Gauge PBR - Ash Gray

- GENERAL NOTES:
1. INSTAL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
 4. AFTER INSTALLATION, WIFE ALL PANELS CLEAN OF METAL SHAWINGS CAUSED BY DRILLING.

| ISSUE | DATE | DESCRIPTION | BY | CHK'D | DSN |
|-------|----------|--------------------------|-----|-------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



MESCO Building Solutions

5244 Bear Creek Court
Irving, TX 75061
Voice 214-687-9999 Fax 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SIMQUE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

CAD: 12/ 6/19

OWNER: TRUCK STOP 75

DATE: 12/ 6/19


SCALE: N.T.S.

PHASE: 1

BUILDING ID: A

JOB NUMBER: 17-B-46005

SHEET NUMBER: E6



David S. HARLEY
DAVIDSON
No. 38306
STATE OF FLORIDA
PROFESSIONAL ENGINEER

Dec 13, 2019

Drawing has been digitally signed.


| SPICE PLATE & BOLT TABLE | | | | | | |
|--------------------------|-----|-----|-----|-----|------|--------|
| Mark | Qty | Top | Bot | Int | Type | Dio |
| SP-1 | 4 | 4 | 4 | 2 | A325 | 7/8" |
| SP-2 | 4 | 4 | 4 | 2 | A325 | 3/4" |
| | | | | | | 2 3/4" |
| | | | | | | 8" |
| | | | | | | 3/4" |
| | | | | | | 1/2" |
| | | | | | | 2'-5" |

| STIFFENER TABLE | | | |
|-----------------|-------|-------|------------|
| Mark | Stiff | Width | Plate Size |
| RF3-1 | St- 1 | 4" | 1/4" |
| RF3-3 | St- 1 | 4" | 1/4" |

| BASE PLATE TABLE | | | |
|------------------|-------|-------|--------|
| Col | Width | Thick | Length |
| BP-1 | 8" | 3/8" | 1'-1" |

FLANGE BRACES: BOTH SIDES(UNLESS NOTED)
FBx(A1): xx=length(in)
FB6 - 12X2X1/8"
A - 12X2X1/46

| MEMBER TABLE | | | |
|--------------|------------------------|----------------|-----------------|
| Mark | Web Depth | Web Plate | Outside Flange |
| RF3-1 | Start/End 12.0/23.9 | Thick 0.250 | Length 120.0 |
| RF3-2 | Start/End 23.9/34.0 | Thick 0.313 | Length 102.5 |
| RF3-3 | Start/End 16.0/22.0 | Thick 0.156 | Length 240.0 |



FRAME CROSS SECTION: FRAME LINE 3

| ISSUE | DATE | DESCRIPTION | BY | CHK'D | DSN |
|-------|----------|--------------------------|-----|-------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |

MESCO Building Solutions
5244 Bear Creek Court
Voice 214-687-9999
Irving, TX 75061
Fax 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SIMQUE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

DATE: 12/ 6/19

SCALE: N.T.S.

PHASE: 1

BUILDING ID: A

JOB NUMBER: 17-B-46005

SHEET NUMBER: E9

ISSUE: 0

Dec 13, 2019

David S. Davidson


FLORIDA PROFESSIONAL ENGINEER

No. 38305

| SPICE PLATE & BOLT TABLE | | | | | | |
|--------------------------|-----|-----|-----|------|------|------|
| Mark | Qty | Top | Bot | Int | Type | Dia |
| SP-1 | 4 | 4 | 4 | 2 | A325 | 7/8" |
| SP-2 | 4 | 4 | 2 | A325 | 3/4" | 2" |
| | | | | | | 8" |
| | | | | | | 3/4" |
| | | | | | | 2-5" |

| STIFFENER TABLE | | | |
|-----------------|-------|-------|----------|
| Mark | Stiff | Width | Length |
| RF4-1 | St- 1 | 4" | 33 15/16 |

| BASE PLATE TABLE | | | |
|------------------|------------|-------|--------|
| Col | Plate Size | | Length |
| Mark | Width | Thick | |
| BP-1 | 8" | 3/8" | 1'-1" |



FLANGE BRACES: BOTH SIDES(UNLESS NOTED)
FBxxA(1): xx=length(in)
FB6 - 12X21/8
A - 12X21/46

| MEMBER TABLE | | | |
|--------------|-----------|-----------|----------------|
| Mark | Web Depth | Web Plate | Outside Flange |
| RF4-1 | 12.0/23.9 | 0.250 | 120.0 |
| RF4-2 | 23.9/34.0 | 0.313 | 102.5 |
| | 34.0/34.0 | 0.313 | 36.1 |
| | 32.0/27.3 | 0.250 | 50.0 |
| | 27.3/16.0 | 0.185 | 120.0 |
| | 16.0/16.0 | 0.156 | 120.0 |
| | 16.0/22.0 | 0.156 | 240.0 |

FRAME CROSS SECTION: FRAME LINE 4

GENERAL NOTES:

1. SNUG TIGHT - ALL BOLTED JOINTS WITH A325 TYPE 1 BOLTS ARE SPECIFIED AS SNUG-TIGHTENED JOINTS IN ACCORDANCE WITH THE SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS, DECEMBER 31, 2009. PRE-TENSIONING METHODS, INCLUDING TURN-OF-NUT, CALIBRATED WRENCH, TWIST-OFF-TYPE TENSION-CONTROL BOLTS OR DIRECT TENSION INDICATOR ARE NOT REQUIRED. INSTALLATION INSPECTION REQUIREMENTS FOR SNUG TIGHT BOLTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.1) IS SUGGESTED.
2. ALL FIELD WELDED CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 MACHINE BOLTS
3. INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN

| ISSUE | DATE | DESCRIPTION | BY | CHK'D | DSN |
|-------|----------|--------------------------|-----|-------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |

MESCO Building Solutions

5244 Bear Creek Court
Voice 214-687-9999

Irving, TX 75061
Fax 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SIMQUE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

OWNER: TRUCK STOP 75

CAD DATE SCALE PHASE BUILDING ID JOB NUMBER SHEET NUMBER

12/ 6/19 N.T.S. 1 A 17-B-46005 E10

Dec 13, 2019

PROFESSIONAL ENGINEER


STATE OF FLORIDA

No. 38305

| SPICE PLATES & BOLTS | | | | | | Plate Size | | |
|----------------------|------|----------|------|------|--------|------------|-------|------------|
| Splice Mark | Quan | Top/ Bot | Type | Dia | Length | Width | Thick | Length |
| SP- 1 | 4 | 4 | A325 | 3/4" | 2" | 8" | 1/2" | 1'-10 1/4" |

| STIFFENER TABLE | | | |
|-----------------|------------|------------------|-------------------------|
| Mark | Stiff Mark | Plate Size Width | Plate Size Thick Length |
| WF-1 | St- 1 | 4" | 1/4" 14" |


| BASE PLATES | | | |
|-------------|-------|------------------|-----------|
| Col Mark | Width | Plate Size Thick | Length |
| BP- 1 | 8" | 3/8" | 1'-2 1/2" |



| MEMBER SIZE TABLE (in) | | | | | | OUTSIDE FLANGE | | INSIDE FLANGE | |
|------------------------|--------|-----------|-----------|------------|-----------------------|-----------------------|-----------------------|-----------------------|-----------------------|
| MARK | LENGTH | WEB DEPTH | WEB PLATE | THICK | LENGTH | W x T x LENGTH | W x T x LENGTH | W x T x LENGTH | W x T x LENGTH |
| WF-1 | 252.7 | 14.0/14.0 | 0.185 | 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" |
| WF-2 | 197.5 | 14.0/14.0 | 0.185 | 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" |

- GENERAL NOTES:
1. SNUG TIGHT - ALL BOLTED JOINTS WITH A325 TYPE 1 BOLTS ARE SPECIFIED AS SNUG-TIGHTENED JOINTS IN ACCORDANCE WITH THE SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS, DECEMBER 31, 2009. PRE-TENSIONING METHODS, INCLUDING TURN-OF-NUT, CALIBRATED WRENCH, TWIST-OFF-TYPE TENSION-CONTROL BOLTS OR DIRECT TENSION INDICATOR ARE NOT REQUIRED. INSTALLATION INSPECTION REQUIREMENTS FOR SNUG TIGHT BOLTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.1) IS SUGGESTED.
 2. ALL FIELD WELDED CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 MACHINE BOLTS
 3. INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN

| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|----------|--------------------------|-----|------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



MESCO Building Solutions

5244 Bear Creek Court
Irving, TX 75061
Voice 214-687-9999 Fax 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SIMQUE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

CAD: 12/ 6/19

DATE: 12/ 6/19

N.T.S.

SCALE: 1

PHASE: A

BUILDING ID: 17-B-46005

JOB NUMBER: 17-B-46005

SHEET NUMBER: E13

ISSUE: 0

Dec 13, 2019

Drawing has been digitally signed.

Harley Davidson

FLORIDA PROFESSIONAL ENGINEER

No. 38305

STATE OF FLORIDA

| SPICE PLATES & BOLTS | | | | | | |
|----------------------|------|------|-----|------------|-------|------------|
| Splice Mark | Quan | Top/ | Bot | Type | Dia | Length |
| SP- 1 | 4 | 4 | 4 | A325 | 3/4" | 2" |
| | | | | Plate Size | Thick | length |
| | | | | 8" | 1/2" | 1'-10 1/4" |

| STIFFENER TABLE | | | |
|-----------------|-------|-------|---------------------------------|
| Mark | Stiff | Width | Plate Size Thick length |
| WF-1 | St- 1 | 4" | 1/4" 14" |


| BASE PLATES | | | |
|-------------|-------|---------------------|-----------|
| Col Mark | Width | Plate Size Thick | length |
| BP- 1 | 8" | 3/8" | 1'-2 1/2" |

- GENERAL NOTES:
1. SNUG TIGHT – ALL BOLTED JOINTS WITH A325 TYPE 1 BOLTS ARE SPECIED AS SNUG-TIGHTENED JOINTS IN ACCORDANCE WITH THE SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS, DECEMBER 31, 2009. PRE-TENSIONING METHODS, INCLUDING TURN-OF-NUT, CALIBRATED WRENCH, TWIST-OFF-TYPE TENSION-CONTROL BOLTS OR DIRECT TENSION INDICATOR ARE NOT REQUIRED. INSTALLATION INSPECTION REQUIREMENTS FOR SNUG TIGHT BOLTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.1) IS SUGGESTED.

2. ALL FIELD WELDED CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 MACHINE BOLTS

3. INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN

| MEMBER SIZE TABLE (in) | | | | | | | | | |
|------------------------|--------|-----------|-------|-----------|------------|-----------------------|-----------------------|-----------------------|-----------------------|
| MARK | LENGTH | WEB DEPTH | | WEB PLATE | | OUTSIDE FLANGE | | INSIDE FLANGE | |
| | | START/END | THICK | THICK | LENGTH | W x T x LENGTH | W x T x LENGTH | W x T x LENGTH | W x T x LENGTH |
| WF-1 | 252.7 | 14.0/14.0 | 0.185 | 0.185 | 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" | 8 x 1/4" x 21'-0 3/4" |
| WF-2 | 197.5 | 14.0/14.0 | 0.185 | 0.185 | 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" | 6 x 1/4" x 16'-5 1/2" |



ISSUE

DATE

DESCRIPTION

BY

CHK'D

DSN

0

12/ 6/19

FOR ERECTOR INSTALLATION

LSN

PNR

STK

MESCO Building Solutions

5244 Bear Creek Court
Voice 214-687-9999

Irving, TX 75061
Fax 214-687-9737

PROJECT:

TRUCK STOP 75

CUSTOMER:

SIMQUE CONSTRUCTION

LOCATION:

LAKE CTRY, FL 32024

OWNER:

TRUCK STOP 75

CAO

DATE

SCALE

PHASE

BUILDING ID

JOB NUMBER

SHEET NUMBER

ISSUE

12/ 6/19

N.T.S.

1

A

17-B-46005





E14

0

Dec 13, 2019

Drawing has been digitally signed.

David S. HARLEY DAVIDSON
No. 38305
STATE OF FLORIDA
PROFESSIONAL ENGINEER






A10
Purlin To Rigid Frame

B19
Endwall Column To Rigid Frame Rafter

M3
Header To Cold Form Jamb/Sub Jamb

Q2
Cable Brace Attachment At Web



J24
Eave Strut To By-Pass Rigid Frame At Endwall

K3
Girt To Single Cold Form Jamb/Sub Jamb

L8
Single Cold Form Jamb/Sub Jamb To Girt

Page MB-J24

J24

Date Jun '17

Rev 00

Page MB-K3

K3

Date Dec '17

Rev 00

Page MB-L8

L8

Date Jun '17

Rev 00

Page MB-A10

A10

Date Nov '19

Rev 01

Page MB-B19

B19

Date Nov '19

Rev 01

Page MB-M3

M3

Date Dec '17

Rev 00

Page MB-Q2

Q2

Date Mar '18

Rev 01

DESCRIPTION

FOR ERECTOR INSTALLATION

DATE

12/ 6/19

ISSUE

0

BY

LSN

CK'D

PNR

DSN

STK

PROJECT:

TRUCK STOP 75

CUSTOMER:

SIMQUE CONSTRUCTION

LOCATION:

LAKE CITY, FL 32024

OWNER:

TRUCK STOP 75

CAO

DATE

12/ 6/19

SCALE

N.T.S.

PHASE

1

BUILDING ID

A

JOB NUMBER

17-B-46005

SHEET NUMBER

DET1

ISSUE

0

MESCO Building Solutions

5244 Bear Creek Court

Voice 214-687-9999

Fax 214-687-9737

Irving, TX 75061

Dec 13, 2019

Drawing has been digitally signed.


STATE OF FLORIDA

PROFESSIONAL ENGINEER


NO. 38305

DAVIDSON


SHARLEY




* - Refer To Anchor Rod Setting
Plan For Dimension



| Purlin Lap Dimensions | |
|-----------------------|------------|
| * | ** |
| 1'-5 3/4" | 2'-11 1/2" |
| 2'-5 3/4" | 4'-11 1/2" |
| 3'-1 3/4" | 6'-3 1/2" |



| Girt Lap Dimensions | |
|---------------------|------------|
| * | ** |
| 1'-5 3/4" | 2'-11 1/2" |
| 2'-5 3/4" | 4'-11 1/2" |
| 3'-1 3/4" | 6'-3 1/2" |




ANTI PURLIN ANTI-ROLL CLIP


E5 Door Jamb Base Plate

G2 Purlin To Rigid Frame


H2 Girt To Rigid Frame



| Girt Lap Dimensions | |
|---------------------|------------|
| * | ** |
| 1'-5 3/4" | 2'-11 1/2" |
| 2'-5 3/4" | 4'-11 1/2" |
| 3'-1 3/4" | 6'-3 1/2" |



* - Refer To Anchor Rod Setting
Plan For Dimension




C12 Girt To Hot Rolled
Endwall Column

D16 Girt To Rigid Frame
Endwall Column

E3 Endwall Column Base Plate

| ISSUE | DATE | DESCRIPTION | BY | CHK'D | DSN |
|-------|----------|--------------------------|-----|-------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



MESCO Building Solutions

5244 Bear Creek Court Irving, TX 75061
Voice 214-687-9999 Fax 214-687-9737

PROJECT: TRUCK STOP 75
CUSTOMER: SIMQUE CONSTRUCTION
LOCATION: LAKE CITY, FL 32024

OWNER: TRUCK STOP 75

Dec 13, 2019

CHARLEY DAVIDSON
No. 38305
FLORIDA
PROFESSIONAL ENGINEER

17-B-46005

12/ 6/19

SCALE N.T.S.

DATE 12/ 6/19

CAD

PHASE 1




BUILDING ID A

JOB NUMBER

SHEET NUMBER

ISSUE 0




DET2



U2 Bolts At Rigid Frame Ridge Rafter Connection

U3 Bolts At Rigid Frame Rafter To Column Connection

R2 Anchor Rods At Frame Column



H4 Girt To Rigid Frame

H10 Portal Frame To Rigid Frame Column

J2 Eave Strut To By-Pass Rigid Frame At Interior

| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|----------|--------------------------|-----|------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

MESCO Building Solutions
5244 Bear Creek Court
Irving, TX 75061
Voice 214-687-9999 Fax 214-687-9737

PROJECT: TRUCK STOP 75
CUSTOMER: SINOQUE CONSTRUCTION
LOCATION: LAKE CITY, FL 32024

OWNER: TRUCK STOP 75

Dec 13, 2019

Drawing has been digitally signed.

STATE OF FLORIDA
PROFESSIONAL ENGINEER
No. 38305
HARLEY DAVIDSON

CAD

DATE

SCALE


PHASE

BUILDING ID


JOB NUMBER

SHEET NUMBER

ISSUE



Note: 3/4" Screws must be installed through the Top Sealer to ensure a water tight connection.



PBR Roof Panel

Fixed Ridge Detail




Page

GPBR08003

Rev

Apr '19

04



PBR Roof Panel

End Lap Detail




Page

GPBR04015

Rev

Apr '19

03



| Trim Profile | Southern Standard | Southern Large | Northern Standard | Northern Large |
|--------------|-------------------|----------------|-------------------|----------------|
| Chimney | F719 | F1565 | F7602 | F7160 |
| Chimney | F719 | F4153 | F381 | F7604 |
| Contour | F2219 | F2283 | F2372 | F2400 |
| Signature | F916 | F2633 | F238 | F7618 |

PBR Roof - Gutter Expansion Installation - 100'-0" Maximum


Page

GPBR04003



Rev

May '19

05



| Trim Profile | Southern Standard | Southern Large | Northern Standard | Northern Large |
|--------------|-------------------|----------------|-------------------|----------------|
| Chimney | F719 | F1565 | F7602 | F7160 |
| Chimney | F719 | F4153 | F381 | F7604 |
| Contour | F2219 | F2283 | F2372 | F2400 |
| Signature | F916 | F2633 | F238 | F7618 |



PBR Wall Panel

Base Angle Without Panel Recess




Page

BPW02101X

Rev

Apr '18

02



Dec 13, 2019
Drawing has been digitally signed.

| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|----------|--------------------------|-----|------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

MESCO Building Solutions

5244 Bear Creek Court Irving, TX 75061

Voice 214-687-9999 Fax 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SIMCO CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

OWNER: TRUCK STOP 75

DATE: 12/ 6/19

SCALE: N.T.S.

PHASE: 1

BUILDING ID: A

JOB NUMBER: 17-B-46005

SHEET NUMBER: DE14

ISSUE: 0


STATE OF FLORIDA

PROFESSIONAL ENGINEER

NO. 38305

DAVIDSON

Dec 13, 2019










| Description | Fastener Number | Application |
|-----------------------|-----------------|------------------------------------|
| 1/4"-14 x 7/8" Type 2 | 4A | Stitch & Trim Screw |
| 12-14 x 1 1/4" Type 2 | 17A | Member Screw (Up to 4" insulation) |
| 12-14 x 1 1/2" Type 2 | 17B | Member Screw (Up to 6" insulation) |

Standard Grade

| Description | Fastener Number | Application |
|-----------------------|-----------------|------------------------------------|
| 1/4"-14 x 7/8" Type 1 | 4 | Stitch & Trim Screw |
| 12-14 x 1 1/4" Type 2 | 3 | Member Screw (Up to 4" insulation) |
| 12-14 x 1 1/2" Type 2 | 3A | Member Screw (Up to 6" insulation) |

Long Life



| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|---------|--------------------------|-----|------|-----|
| 0 | 12/6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |

MESCO Building Solutions
5244 Bear Creek Court Irving, TX 75061
Voice 214-687-9999 Fax 214-687-9737

PROJECT: TRUCK STOP 75
CUSTOMER: SIMCO CONSTRUCTION
LOCATION: LAKE CITY, FL 32024

OWNER: TRUCK STOP 75

CAD DATE SCALE PHASE BUILDING ID JOB NUMBER

12/6/19 N.T.S. 1 A 17-B-46005


SHEET NUMBER 0

Dec 13, 2019

Drawing has been digitally signed.

STATE OF FLORIDA
PROFESSIONAL ENGINEER
No. 38305
David S. Harley Davidson


Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023
OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Opening Width and Height before making field cuts and adjust cut dimensions accordingly.


Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023
OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Panel position is shown with Panel Rib and Opening on 1'-0 module. Location of Rib may vary depending on the Opening Width and location. Field measure before cutting Panel and Trim.


Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023
OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Opening Width and Height before making field cuts and adjust cut dimensions accordingly.

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023
OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Panel position is shown with Panel Rib and Opening on 1'-0 module. Location of Rib may vary depending on the Opening Width and location. Field measure before cutting Panel and Trim.

STANDARD FRAMED OPENING DETAILS (PBR WALL PANEL)

CONT.

| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|----------|--------------------------|-----|------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |

MESCO

Building Solutions

5244 Bear Creek Court
Voice 214-687-9999

Irving, TX 75061
Fox 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SIMOLE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

OWNER: TRUCK STOP 75

DATE

12/ 6/19

SCALE

N.T.S.

PHASE

1

BUILDING ID

A

JOB NUMBER

17-B-46005

SHEET NUMBER

DET6

ISSUE

0

Dec 13, 2019


Drawing has been digitally signed.

STATE OF FLORIDA

PROFESSIONAL ENGINEER

No. 38305

CHARLEY DAVIDSON




Note: Field measure Opening Height before making field cuts and adjust cut dimensions accordingly.


Note: Field measure Opening Height before making field cuts and adjust cut dimensions accordingly.

Note: Field measure Opening Height before making field cuts and adjust cut dimensions accordingly.


Note: Trim installation can be done by Field Notch Panel as shown on PW06022 & PW06023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW06024 & PW06025.




Note: Trim installation can be done by Field Notch Panel as shown on PW06022 & PW06023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW06024 & PW06025.




Note: Trim installation can be done by Field Notch Panel as shown on PW06022 & PW06023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW06024 & PW06025.



Note: Trim installation can be done by Field Notch Panel as shown on PW06022 & PW06023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW06024 & PW06025.



| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|----------|--------------------------|-----|------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



MESCO Building Solutions

5244 Bear Creek Court
Voice 214-687-9999

Irving, TX 75061
Fax 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SIMQUE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

DATE: 12/ 6/19

SCALE: N.T.S.

PHASE: 1

BUILDING ID: A


JOB NUMBER: 17-B-46005

SHEET NUMBER: DET8


ISSUE: 0

Dec 13, 2019

Drawing has been digitally signed.



STANDARD FOUR SIDED FRAMED OPENING DETAILS
(PBR WALL PANEL)







PBR Wall Panel - Four Sided Framed Opening
Head and Sill Trim Installation

PBR Wall Panel - Four Sided Framed Opening
Jamb Trim Field Cut Details

PBR Wall Panel - Four Sided Framed Opening
Optional Channel Closure Trim

PBR Wall Panel - Four Sided Framed Opening - Jamb Trim Installation



| ISSUE | DATE | DESCRIPTION | BY | CK'D | DSN |
|-------|----------|--------------------------|-----|------|-----|
| 0 | 12/ 6/19 | FOR ERECTOR INSTALLATION | LSN | PNR | STK |

MESCO Building Solutions

5244 Bear Creek Court
Irving, TX 75061
Voice 214-687-9999 Fax 214-687-9737

PROJECT: TRUCK STOP 75

CUSTOMER: SINOUE CONSTRUCTION

LOCATION: LAKE CITY, FL 32024

CAD

DATE: 12/ 6/19

SCALE: N.T.S.

PHASE: 1

BUILDING ID: A

JOB NUMBER: 17-B-46005

SHEET NUMBER: DET9


ISSUE: 0

Dec 13, 2019

Drawing has been digitally signed.

Building Anchorage

1. To Determine That The Foundation Is Square, Measure Diagonal Dimensions To Be Sure They Are Of Equal Length.
2. To Determine The Location Of The Foundation, Set Up A Transit Or Level And Use A Level Rod To Obtain The Elevation At All Columns.
3. Carefully Check The Location Of All Anchor Rods Against The Anchor Rod Setting Plan Furnished By The Manufacturer. All Dimensions Must Be Identical To Assure A Proper Start-up.




Pre-Erection Notes:

The Following Notes, Procedures And Suggested Recommendations Are Important Parts Of The Pre-Erection Process.



- 1.) Prior To The Time The Erection Crew Arrives, A Responsible Person Should Check The Job Site For Foundation Readiness, Square, And Accuracy And Anchor Rod Size And Location.

The Drawing Shown Below Indicates A Method Which May Be Used To Check The Foundation And Bolts For Square.




Measure Along Adjacent Sides Of Foundation Using A Pair Of Dimensions Shown. If The Diagonal Distance Between These Points Is As Noted, The Corner Is Square. Diagonal Measurements Between Opposite Anchor Rods Will Indicate If These Bolts Are Set Square.

It Is Extremely Important That Anchor Rods Are Placed Accurately And In Accordance With The Anchor Rod Setting Plan. All Anchor Rods Should Be Held In Place With A Template Or Similar Means, So That They Will Remain Plumb And In Correct Location During The Placement Of The Concrete. A Final Check Should Be Made After Completion Of The Concrete Work And Prior To The Installation Of The Wall Panels. This will allow Necessary Corrections To Be Made Before Costly Installation Labor And Equipment Arrives.



Projection Of Anchor Rods (D) Given On Anchor Rod Plan




Dimensions A, B, And C Given On Anchor Rod Plan

AISC Code Of Standard Practice For Steel Building And Bridges Tolerances For Setting Anchor Rods

Anchor Rod Diameter, Inches (mm), *Horizontal Variation, Inches (mm)

$\frac{3}{4}$ " and $\frac{7}{8}$ " (19 And 22 mm) $\frac{1}{4}$ " (6 mm)
 $1\frac{1}{4}$ ", $1\frac{1}{2}$ " (25, 31, 38 mm) $\frac{3}{8}$ " (10 mm)
 $1\frac{3}{4}$ ", 2", $2\frac{1}{2}$ " (44, 50, 63 mm) $\frac{1}{2}$ " (13 mm)



ANCHOR ROD SETTING TOLERANCES


* Horizontal Variations Vary Depending On Anchor Rod Diameter. See Above

Erection Tolerances


ERECTION BRACING:

It Is The Responsibility Of The Erector To Determine, Furnish And Install All Temporary Supports Such As Temporary Guys, Beams, Falswork, Chocking, Or Other Elements Required For The Erection Operation (In Accordance With Section 7.10.3 Of AWS/AISC 303, Code Of Standard Practice For Steel Building And Bridges).


COLUMN ALIGNMENT TOLERANCES



ALIGNMENT TOLERANCE FOR MEMBERS WITH FIELD SPLICES



MEZZANINE BEAM HEIGHT TOLERANCE




General Erection Notes

- 1.) All Structural Framing Members, Purins, Girts, Clips, Flange Braces, Bolts, Bracing Systems, Roof And Wall Panels, Etc. Must Be Installed As Shown On Erection Drawings.
- 2.) It Is Extremely Important, Especially During Construction, That Panels At The Eaves, Rakes And Ridges Be Kept Secure.

Panel Cautions And Notes

To Minimize Potential Of Corrosive Action At The Bottom Edge Of Wall Panels, The Contractor Must Assure That The Following Procedures Are Followed:

- 1.) The Concrete Foundation Should Be Cured For A Minimum Of Seven (7) Days Before Wall Panels Are Installed. (Uncured Concrete Is Highly Alkaline And Metal Panels Can Undergo Varying Degrees Of Corrosive Attack When In Direct Contact With The Concrete.) After The First Week Of The Curing Cycle, The Reaction Between Metallic Coatings On Steel And The Concrete Is Essentially Halted.
- 2.) Top Of Finish Grade At Building To Be A Minimum Of Four (4) Inches Below Bottom Of Panel.
- 3.) Finish Grade Is To Slope Away From Building To Ensure Proper Drainage.
- 4.) Upon Completion Of Finish Grading, All Dirt Is To Be Cleaned From Around Base Of Wall Panel Where It May Have Collected In Panel Notch Or On Base Trim.



Fastener Installation

Correct Fastener Installation Is One Of The Most Critical Steps When Installing Roof/Wall Panels. Drive The Fastener In Until It Is Tight And The Washer Is Firmly Seated. Do Not Over-Tighten. Fasteners Of Wesspace Around The Washer Is A Good Visual Tightness Check. Always Use The Proper Tool To Install Fasteners. A Fastener Driver (Screw Gun) With A RPM Of 1700-2000 Should Be Used For Self-Drilling Screws. A 500-600 RPM Fastener Driver Should Be Used For Self-Tapping Screws. Discard Worn Sockets, These Can Cause The Fastener To Wobble During Installation.

Note: Always Remove Metal Filings From Surface Of Panels At The End Of Each Work Period. Rusting Filings Can Destroy The Paint Finish And Void Any Warranty.



Tape And Tube Sealant

Proper Tape And Tube Sealant Application Is Critical To The Weather Tightness Of A Building. Tape Sealant Should Not Be Strained When Installed. Apply Only To Clean, Dry Surfaces. Keep Only Enough Sealants On The Roof That Can Be Installed In A Day. During Warm Weather, Store Sealants In A Cool Dry Place. During Cold Weather (Below 60°) Sealants Must Be Kept Warm (60°-90°) Until Application. After Tape Sealant Has Been Applied, Keep Protective Paper In Place Until Panel Is Ready To Be Installed.


Important Note

All Details, Recommendations And Suggestions Contained In This Erection Guide Of This Drawings Set Are For General Guidelines Only. And Not Meant To Be All-Inclusive. Industry Accepted Installation Practices With Regard To All Areas Not Specifically Discussed In This Section Should Be Followed. Only Experienced, Knowledgeable Installers Familiar With Accepted Practices Should Be Used To Assure A Quality Project.

It Is Emphasized That The Manufacturer Is Only A Manufacturer Of Metal Building Components And Is Not Engaged In The Installation Of Its Products. Opinions Expressed By The Manufacturer About Installation Practices Noted In This Erection Guide Are Intended To Assist The Installer In Obtaining A Quality And Safe Installation And To Assist In Obtaining Customer Satisfaction With The Completed Building Are Determined By The Experience, Expertise, And Skills Of The Installation Crews. As Well As The Equipment Available For Handling The Materials. Actual Installation Operations, Techniques And Site Conditions Are Beyond The Manufacturers Control.

PBR Roof Panels

For PBR Roofs With Ridge Panels, It Is Recommended That Both Sides Of The Ridge Be Sheeted Simultaneously. This Will Keep The Insulation Covered For The Maximum Amount Of Time And The Panel Ribs On Be kept in proper alignment. The Ridge Panel Must Be Installed Last. The Ridge Panel Must Be Installed For The Ridge Panel. This Will Prevent The Insulation From Sagging Or Settling. Can Be Properly Installed. Check For Proper Coverage As The Sheetting Progresses.



Install The First Run Of Roof Panels Across The Building From Eave To Eave Or Eave To Ridge. To Allow Proper Installation Of The Rake Trim, The Starting Location For The First Panel Must Be As Shown In The Rake Details Included With The Erection Drawings. When The First Run Is Properly Located And Aligned With The Correct Endgaps And Cove Overhangs, Fasten To Furlers. Roof Panels Should Be Installed So That The Sidelap Is In A Direction Away From Prevailing Wind. Refer To Appropriate Lap Details Included With The Erection Drawings.

Install Remaining Roof Insulation And Panels. To Avoid Accumulative Error Due To Panel Coverage Gain Or Loss, Properly Align Each Panel Before It Is Fastened. Occasional Checks Should Be Made To Ensure That Correct Panel Coverage Is Maintained. Special Attention Should Be Given To Fasteners, Sealant and Closure Requirements. Refer To Details Included With The Erection Drawings.

At Finishing End Of Roof, The Last panels May Require Field Modification For Installation Of Rake Trim. Refer To Rake Details included With The Erection Drawings. DO NOT BACK LAP THROUGH FASTENED ROOF PANELS.

NOTE: Roof Types And Installation Requirements Will Vary. Refer To The Appropriate Details For Specific Panel Used.

IMPORTANT: Loose Fasteners, Blind Nails, Drill shavings, Etc.. Must Be Removed From The Roof To Guard Against Corrosion.


Wall Panels

Proper Horizontal And Vertical Alignment Of Supporting Structure (Girts Or Other Framing) Is The Responsibility Of The Installer. Failure To Align The Secondary members Properly Prior To Wall Installation Can Have A Direct Impact On The Final Appearance And Performance Of The Installed Wall System For Which The Metal Building Manufacturer Is Not Responsible.

Before Installing Wall Panels, The Girts Must Be Aligned To A Level Position So That There Is No Visible Sag. This Should Be Done Directly Ahead Of Panel Installation.

Girt Leveling May Be Accomplished By Standing A Section Of Gable Angle Vertically Against The Outside Girt Flanges At Approximate Mid-bay Location. When Girts Are Level, Attach The Girt Flanges To The Angle With Vise Grip Pliers Or Temporary Screws. Wood Blocking Cut To Fit The Spaces May Also Be Used For Alignment.

Note: Temporary Girt Blocking Is Not Recommended On Concealed Fastener Panels. The Removal Of The Blocks After Panel Installation Can Cause Oil Canning.





Note: Wall Panel Type And Installation Details Will Vary. Refer To The Erection Drawings And Details For The Specific Panel Used For Your Building.



If Walls Are To Be Insulated With Blanket Insulation Over Girt Girt Flanges, Base And Cove, Place A Continuous Run Of Contact Tape Along The Eave Strut And Base Member.


Note: At The Base Cut Off The Insulation A Minimum Of 1/2" Above The Bottom Of The Wall Panel. This Will Prevent The Insulation From Hanging Below The Wall Panel And Holding Moisture.

Note: Additional Insulation May Be Required To Fill The Space Between The Roof Panel And The Wall Panel To Prevent Condensation In Certain Climate Regions




Sidelap Panels Should Be Installed So That The Panel Sidelap Is In A Direction Away From The Prevailing Wind. Refer To Appropriate Lap Detail included With Erection Drawings.)

Note: Check Periodically To Ensure That All Panels Are Aligned And Plumb.



Note: After Drilling Panels, It Is Important To Clean Metal Flings Off All Panel Surfaces, Including Between Panels That Are Not Installed That Day, To Avoid Rust Stains.

Suggested Method Of Purlin Attachment For Building Accessories




• Denotes Material Not Provided By Metal Building Manufacturer.

The Total Hanger Load Shall Not Exceed The Design Colateral Load For The Building. Example: 5'-0" (Purlin Spacing) X 5'-0" (Hanger Spacing) X 6 PSF (colateral Load) = 150 Lbs.

See Cover Sheet For Design Colateral Load For This Building.

Note: If The Building Is Designed For 0 PSF Colateral Load, Then Adding Any Suspended System (I.e. Duct Work, Piping, Lights, Ceilings, Etc.) Will Correspondingly Reduce The Design Live Load.

Roof Curbs When Not Supplied By Building Manufacturer



The Curb Details Shown Illustrate The Building Manufacturers Recommended Curb Style And Installation Method. It Is The Erector/Installer's Responsibility To Provide The Proper Curb Style And Install Them In Accordance With The Procedures Established By These Details. Failure By The Erector/Installer To Follow These Recommendations May Result In The Curbs Damaging The Roof System Or Excluded From Warranties.


All Roof Curbs To Be:

1. .080 Aluminum Or 18 Ga. Stainless Steel (No Galvalume® Or Galvalume®)
2. Panel Rib To Panel Rib (No Flat Skirt Or Lay-Over Curbs).
3. Installed With Down Hill End Over Panel And Up Hill End Under Panel Application For Water Flow At Panel Splice.
4. Up Lift Prevention For Clip Applied Roof Systems Are Required If:
 - a. Wind Loads Exceed 110 MPH.
 - b. Curb Base Crosses A Purlin.
5. Supported on (4) Stays By Primary Or Secondary Framing.
6. Maximum Single Curb Weight Recommended Is 1500 Lbs.

Roof Jack Installation when Not Supplied By Building Manufacturer

General Installation Notes

- ? Do Not Use Galvanized Roof Jacks, Lead Hots, Or Other Residential Grade Roof Jacks. These Roof Jacks Do Not Have 20 Year Service Life And In Cases Of Lead Hots Will Cause Galvanic Corrosion Of The Roof Panel.
- ? Use EPDM Rubber Roof Jacks With An Integral Aluminum Band Bonded Into The Perimeter Of The Base. EPDM Roof Jacks Have A Temperature Range From -65° To 212°F. Use Silicone Roof Jacks For High Temperatures. Silicone Roof Jacks Have A Temperature Range Of -100°F To 437°F.
- ? Retrofit Roof Jacks Are Available For Applications In Which The Top Of The Pipe Is Inaccessible, Eliminating The Possibility Of Sliding The Roof Jack Over The Top Of The Pipe.
- ? Do Not Use Tube Sealant To Seal The Roof Jack To The Roof Panels. Use Roll Tape Sealer Between The Roof Jack And The Roof Panel And Attach The Roof Jack To The Roof Panel With Fastener #4 1/4 x 1/4 x 1/4 LL SD W/Washer At 1" O.C. Around The Base Of The Roof Jack. See Table Below For Quantities.
- ? The Top Of The Roof Jacks For The Fasteners Must Be Spaced Down The Roof Jack Over The Pipe And Under The Tape Sealer For The Fasteners Of The Roof Jack Base Between The Roof Jack And The Roof Panel. Apply Tape Sealer Around The Pipe And Install A Stainless Steel Clamp (Not By Bldg. Mfr.) Over The Top Of The Roof Jack And Firmly Tighten To Form A Secure Compression Seal.
- ? If The Pipe Diameter Is So Large To Block The Flow Of Water Down The Roof Panel, A Flat Base Roof Jack Must Be Installed Into The Roof And The Roof Jack Will Be Sealed To The Curb. A Two Piece Curb May Be Required When The Top Of The Pipe Is Inaccessible.
- ? In Northern Climates, The Pipe Penetration Should Be Protected From Moving Ice Or Snow With A Snow Retention System Immediately Up Slope From The Pipe.



Install Pipe in Center To Allow Base Of Roof Jack To Lay Flat on Panel. Cannot Overlap More Than 75% Of Panel.

