

BEARING HEIGHT SCHEDULE

8'-0"

6 1/2 PITCH

2' OH

NOTES :

- 1) REFER TO HB 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING) REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED
- 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO REINFORCED CONCRETE FOR ALTERNATE BRACING REQUIREMENTS
- 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER
- 4) ALL TRUSSES ARE DESIGNED FOR 2.0 c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED
- 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED
- 6) 5/42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP
- 7) ALL ROOF TRUSS HANGERS TO BE SWIPSON HBS26 UNLESS OTHERWISE NOTED. ALL FLOOR TRUSS HANGERS TO BE SWIPSON TMA422 UNLESS OTHERWISE NOTED
- 8) BEARING ADJUSTMENT (BPA) TO BE FURNISHED BY BUILDER

SHOP DRAWING APPROVAL

THIS LAYOUT IS THE SOLE SOURCE FOR FABRICATION OF TRUSSES AND VARIOUS ALL PREVIOUS ARCHITECTURAL OR OTHER TRUSS LAYOUTS. REVIEW AND APPROVAL OF THIS LAYOUT MUST BE RECEIVED BEFORE ANY TRUSSES WILL BE BUILT. VERIFY ALL CONDITIONS TO INSURE AGAINST CHANGES THAT WILL RESULT IN EXTRA CHARGES TO YOU.

Engineered Bearing Date: \_\_\_\_\_

Approved By: \_\_\_\_\_ Date: \_\_\_\_\_



Burnell

PHONE 904-437-3349 FAX 904-437-3994

Jacksonville

PHONE 904-772-6100 FAX 904-772-1973

Lake City

PHONE 904-755-6894 FAX 904-755-7973

Sanford

PHONE 407-322-0059 FAX 407-322-5553

BUILDER

JOHN NORRIS

DEMPSEY RES.

MADISON

DATE 9-27-06

BY K.L.H. L212216