



111

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 800-2333
CARL A. BROWN, PE - FL # 56126
SCOTT LEWIS KOWALSKI, PE - FL # 77756

100% Employee Owned
myTSGhome.com



111

SIGNATURE & SEAL
9/16/2025

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contained within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition.

Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

ADAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

100 WEST GARDEN STREET

PENSACOLA FL 32502


Division Location: GAINESVILLE

aurel Lake

35	Community: Preserve at	Plan Name: 2240	Project Address: 525 SW Bellflower Lake City FL	Client No.:
			Project No: 	
			Sheet No: 	
2				
FLOOR PLAN				

NOTE:  INDICATES OPENINGS WIND
PRESSURES. SEE WIND LOADING
CRITERIA ON COVER SHEET FOR
INFORMATION.

WALL LEGEND



GENERAL NOTES

302.6 (table 302.6) If water based ceiling texture material is used, Provide $\frac{1}{2}$ " gypsum board for 16" O.C. framing, or $\frac{5}{8}$ " gypsum board for 24" O.C. Framing. Note $\frac{1}{2}$ " sag-resistant gypsum board may be used I.L.O. $\frac{8}{8}$ " gypsum board. $\frac{5}{8}$ " type "X" gypsum board must be stalled on garage ceiling beneath habitable room(s).

302.5.2 Duct Penetration. Ducts in the garage and ducts penetrating the walls or ceilings separating the dwelling from the garage shall be constructed of a minimum No. 26 gage (0.48 mm) sheet steel, 1 inch minimum rigid nonmetallic class 0 or class 1 duct board, other approved material and shall not have openings to the garage.

302.5.1 Door from garage into house must be a minimum 1 $\frac{3}{8}$ " solid wood door, solid or honeycombcore steel door, or 20 Minute fire rated door.

302.7 Enclosed space under stairs that is accessed by door or access panel shall have walls, under-stair surface and any soffits protected on the enclosed side with $\frac{1}{2}$ " gypsum board.

Outdoor swimming pools shall be provided with a barrier complying with R4501.17.1.1 through R4501.17.1.14.

Bathroom exhaust fans must vent to the exterior of the building, exhaust to attic space and soffits is not acceptable. Ventilation shall be permitted to exit through the soffit if solid soffit is installed 5'-0" on each side of the venting.

302.6 The garage shall be separated from the residence and it's attic as required by Table R302.6. From the residence and attics by not less than 1/2-inch (12.7mm) gypsum board applied to the garage side. Garage beneath rooms shall be separated from all habitable rooms above by not less than $\frac{5}{8}$ inch (15.9mm) type X gypsum board or equivalent. Where the separation is a floor-ceiling assembly, the structure supporting the separation shall also be protected by not less than 1/2 inch (12.7mm) gypsum board or equivalent.

312.2.1 Window sills. In dwelling units, where the bottom

312.2.1 **Window sills.** In dwelling units, where the bottom of the clear opening of an operable window opening is located less than 24 inches (610 mm) above the finished floor and greater than 72 inches (1829 mm) above the finished grade or other surface below on the exterior of the building, the operable window shall comply with one of the following:

- Operable windows with openings that will not allow a 4-inch diameter (102 mm) sphere to pass through the opening where the opening is in its largest opened position.
- Operable windows that are provided with window fall prevention devices that comply with ASTM F2090.
- Operable windows that are provided with window opening control devices that comply with Section R312.2.2.

308.4.2 All windows within 2'-0" of doors and in shower or tub areas will be safety tempered glass.

EC: R402.2.4 Vertical or horizontal access doors from conditioned spaces to unconditioned spaces such as attics and crawl spaces shall be weatherstripped and insulated to a level equivalent to the insulation on the surrounding surfaces

M1502.4.5 **Duct length**

The maximum allowable exhaust duct length shall be determined by one of the methods specified in sections M1502.4.5.1 through M1502.4.5.3

M1502.3 **Duct termination.**

Exhaust ducts shall terminate on the outside of the building. Exhaust duct terminations shall be in accordance with the dryer manufacturer's installation instructions. If the manufacturer's instructions do not specify a termination location, the exhaust duct shall terminate not less than 3 feet (914 mm) in any direction from openings into buildings, including openings in ventilated soffits. Exhaust duct terminations shall be equipped with a backdraft damper.

• Porch Ceilings: (See plan for the following options)

• Option 1. Gypsum:
1/2" exterior gypsum soffit board shall be attached to all framing members with 2x blocking provided at perimeter and panel edges.
The gypsum board shall be attached w/ Type "W" 1 1/4" drywall screws at 8" O.C. in field and edges.

• Option 2. Plaster Base:
1/16" OSB on underside of roof trusses shall be attached to all framing members with 2x blocking provided at perimeter and panel edges. The OSB shall be attached w/ 8d nails at 6" O.C. field and 4" O.C. at edges or 7d screw shank 3" O.C. field and 4" edges.

Energy Code Compliance Path is Performance Based Path.
Code cycle is FBC 2023 8th Edition.

* ALL INTERIOR AND EXTERIOR
WALL FRAMING, INCLUDING
FURRING STRIPS ON CMU WALLS,
TO BE SPACED AND 16" O.C. (U.N.O.)

AREA CALCULATIONS

1ST FLOOR	2177 S.F.
TOTAL LIVING (AC)	2177 S.F.
GARAGE	420 S.F.
COVERED ENTRY	134 S.F.
COVERED PATIO/LANAI	
TOTAL AREA UNDER ROOF	2847 S.F.

FLOOR PLAN

MASTER BA. OPTIONS

3040 (1) PC. FIBERGLAS SHOWER IN LIEU OF LINEN CLOSET W/ (1) L.E.D. LT.

Y	N	MASTER BA. OPTIONS
		3040 (1) PC. FIBERGLAS SHOWER IN LIEU OF LINEN CLOSET W/ (1) L.F.D. LT.

OPT. MASTER BATH

SCALE: 1/4" = 1'-0"



Waking Dreams Come True

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 800-2333
CARL A. BROWN, PE - FL # 56126
SCOTT LEWKOWSKI, PE - FL #78750

100% Employee Owned
myTSGhome.com



9/16/2025

o the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain within these drawings comply with the 2023 Florida Building Code- Residential 8th Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.

ADAMS HOMES

FLORIDA CONTRACTORS LICENSE NO. CRC1330146

100 WEST GARDEN STREET

PENSACOLA FL 32502

GAINESVILLE

Division Location:

35	community:	Preserve at Laurel Lake
	an Name:	2240
	object Address:	25 SW Bellflower Dr.
	ake City FL	lient No.:


FOUNDATION PLAN

Project No: _____

Sheet No: _____



3

**NOTE:
SEE SHEET 3.1 FOR
SCHEDULES & DETAILS**



FOUNDATION PLAN

SCALE: 1/4" = 1'-0"
ELEVATION "B"



FLORIDA CONTRACTORS LICENSE NO. CR0130146

 100 WEST GARDEN STREET
 PENSACOLA FL 32502

GAINESVILLE

Division Location:

Builder:

To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contain herein are drawings and plans for the 2023 Florida Building Code-Required Drawings.


Engineer's signature and seal is only for the structure engineering portions of the drawing pages bearing engineer's signature and seal.



Making Dreams Come True

TOTAL SOLUTIONS GROUP
258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 800-2333
CARL A. BROWN, PE - FL # 56128
SCOTT LEWKOWSKI PE - FL #78750

100% Employee Owned
myTSHome.com




SIGNATURE & SEAL
9/1/6/2025
To the best of the Engineer's knowledge, information and belief, the structural plans on these drawings comply with the 2023 Florida Building Code-Residential 8th Edition.
This seal is a representation only for the structural engineer's portions of the drawing pages bearing engineer's signature and seal.

FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502
Division Location: GAINESVILLE
Builder: ADAMS HOMES
Division: GAINESVILLE

Lot: 35 Bldg: UNIT:
Community: Preserve at Laurel Lake
Project Address: 2240 SW Bayflower Dr
Client Name: 2240
Project No:
Sheet No:
5

Project No:
Sheet No:
5
ELEVATIONS "B"



LEFT ELEVATION "B"


SCALE: 3/16" = 1'-0"

VENTILATION CALCULATION	
Calculations shown below are for both, off ridge and ridge vent systems. Only ONE system is required. See builder's specs for product used.	
Formula = SF / 300 * 144 = net sq. inches of venting needed. (Based on the 1/300 exception for the minimum vent area).	
sf. of Area to be vented (SF)	2847
Total needed for exhaust for upper 1/3 Upper = 45% approx.	615 net sq inches
Total needed for intake (soffit area, lower) Lower = 55% approx.	752 net sq inches
Total needed combined to be no less than 40% and no more than 50%	1367 Upper 1/3 = 45% net sq in / sf
Soffit product provides	6.57 net sq in / sf
Overhang distance	2.00 ft
sq in per linear foot of soffit	13.14 sq in / lf
Linear Feet of Soffit needed to meet required	58
Linear Feet of Soffit provided by plan	233
Option one (Ridge vents)	
Ridge vent provides	18.00 net sq in / lf
sf. of Ridge Vent needed	35
Option two (Off ridge vents)	
Off ridge vent provides	138.00 net sq in / sf
Number of Off Ridge Vents for upper 1/3	31



RIGHT ELEVATION "B"

SCALE: 3/16" = 1'-0"





REAR ELEVATION

SCALE: 1/4" = 1'-0"



FRONT ELEVATION "B"

SCALE: 1/4" = 1'-0"



SIMPSON - CONNECTOR SCHEDULE			USP - CONNECTOR SCHEDULE					
MARK	TYPE	CONNECTOR & FASTENERS	SPF	SVP	CONNECTOR & FASTENERS	SPF	SVP	
Ⓐ	FRAME TO MASONRY	HETARW w/ (10) 1/2" x 1 1/2" OR HETARW w/ (9) 1/2" x 1 1/2"	1810		HTARW w/ (10) 1/2" x 1 1/2" OR HTARW w/ (9) 1/2" x 1 1/2"	1885	1870	
Ⓑ	FRAME TO MASONRY	H2SA w/ (10) 1/2" NAILS	615	700	RT2A w/ (10) 1/2" NAILS	515	585	
Ⓒ	FRAME TO FRAME	H10A-2 w/ (10) 1/2" x 1 1/2" AT 2 PLY TRUSSES	1015	1640	RT16-2 w/ (10) 1/2" x 1 1/2" AT 2 PLY TRUSSES	896	1020	
Ⓓ	FRAME TO FRAME	H10A-2 w/ (14) 1/2" x 1 1/2" AT EXTERIOR LOCATION (INCLUDE (6) 1/2" TOENAILS)	850	990	RT16-2 w/ (14) 1/2" x 1 1/2" AT EXTERIOR LOCATION (INCLUDE (6) 1/2" TOENAILS)	1025	1195	
Ⓔ	FRAME TO MASONRY	WOF w/ (2) 1/2" NAILS AND 5/8" A.T.R. W/ 12" EMBEDMENT w/ SIMPSON SET-3G EPoxy	3955	5000	MUG15 w/ (2) 1/2" NAILS AND 5/8" A.T.R. W/ 12" EMBEDMENT w/ SIMPSON SET-3G EPoxy	3350	4495	
Ⓕ	FRAME TO FRAME	H10A-2 w/ (2) 1/2" x 1 1/2" AT EXTERIOR LOCATION (INCLUDE (6) 1/2" TOENAILS)	1215	1415	RT20 w/ (2) 1/2" x 1 1/2" AT EXTERIOR LOCATION (INCLUDE (6) 1/2" TOENAILS)	1285	1530	
Ⓖ	FRAME TO MASONRY	[2] HT320 w/ (6) 1/2" x 1 1/2" AT EXTERIOR LOCATION (INCLUDE (6) 1/2" TOENAILS)	2420	2830	[2] HTW20 w/ (6) 1/2" x 1 1/2" AT EXTERIOR LOCATION (INCLUDE (6) 1/2" TOENAILS)	2570	3060	
Ⓗ	FRAME TO MASONRY	FG300 w/ (3) 1/2" SDS WOOD SCREWS AND (2) 1/2" WEDGE-BOLTS	3400	4725	FG300 w/ (3) 1/2" SDS WOOD SCREWS AND (4) 3/8" x 6" WEDGE-BOLT	7100		
Ⓘ	FRAME TO MASONRY	(1) LGOT w/ (16) 1/2" SINKERS 8 x 1/4" x 3-1/4" TITEN	1755	2140	(2) LGOT2 w/ (32) 1/2" SINKERS & (10) 1/4" x 3" WEDGE-BOLT TO 2 PLY TRUSS	3100-M	3490-M	
Ⓛ	FRAME TO MASONRY / FRAME	(1) LGOT w/ (32) 1/2" SINKERS & (14) 1/4" x 3" WEDGE-BOLTS	3500-M	4020-F	(1) LGOT3 w/ (32) 1/2" SINKERS & (2) LGOT3 w/ (32) 1/2" SINKERS & (10) 1/4" x 3" WEDGE-BOLTS	3500-F	4020-F	
Ⓜ	FRAME TO MASONRY / FRAME	(2) LGOT w/ (32) 1/2" SINKERS & (8) 1/4" x 3" TITEN (2 PLY TRUSS)	4734-M	5670-M	SCREWS 3/4 x 3" 5/8" x 1/2" (2 PLY TRUSS) OR (56) 1/2" SINKERS FOR FRAME (EA)	6480-F	7160-F	
Ⓝ	BEAM TO BEAM	HB410 OPT HUC410 w/ (16) 1/2" x 1 1/2" NAILS	5910-F	6960-F	HB410 OPT HUC410 w/ (16) 1/2" x 1 1/2" NAILS	5910-F	6960-F	
Ⓣ	BEAM TO MASONRY	HB410 OPT HUC410 w/ (18) TITEN	6185-F	7100-F	HB410 OPT HUC410 w/ (18) TITEN	6185-F	7100-F	
Ⓤ	BEAM TO MASONRY / FRAME	HB410 OPT HUC410 w/ (18) 1/2" NAILS & (12) 1/4" x 2 3/4" TITEN (TO MAS.) OR (12) 1/4" x 2 3/4" TITEN (TO FRAME)	62165	71135	HB410 OPT HUC410 w/ (18) 1/2" NAILS & (12) 1/4" x 2 3/4" TAPCON (TO MAS.) OR (12) 1/4" x 2 3/4" TAPCON (TO FRAME)	6185-F	7100-F	
Ⓛ	FRAME TO MASONRY	HT10S w/ (8) 1/2" NAILS AND (2) 3/8" x 4" 2-PLY w/ (12) 1/2" NAILS	1920	1935	HT10S w/ (8) 1/2" NAILS AND (2) 3/8" x 4" 2-PLY w/ (12) 1/2" NAILS	1920	1935	
Ⓜ	FRAME TO MASONRY	HT10S w/ (8) 1/2" NAILS AND (4) 1/4" x 2 1/4" TITEN	955	1110	HTW11W w/ (8) 1/2" NAILS AND (4) 1/4" x 2 1/4" WEDGE-BOLT	1145	1225	
Ⓝ	FRAME TO MASONRY	HTSM20 w/ (10) 1/2" NAILS AND (4) 1/4" x 2 1/4" TAPCON	955	1110	HTW20 w/ (10) 1/2" NAILS AND (4) 1/4" x 1 3/4" TAPCON	1145	1225	
Ⓣ	FRAME TO MASONRY	HTD72 w/ (14) 1/2" SDS WOOD SCREWS AND (1) 1/2" x 1 1/2" T.R. EPOXY w/ (2) 3/8" x 4" TITEN HD	785	910	HTD72 w/ (14) 1/2" SDS WOOD SCREWS AND (1) 1/2" x 1 1/2" T.R. EPOXY w/ (2) 3/8" x 4" TITEN HD	785	910	
Ⓛ	FRAME TO MASONRY	HTT4 w/ (29) 1/2" x 1 1/2" NAILS AND (1) 1/2" x 1 1/2" T.R. EPOXY w/ (2) 3/8" x 4" TITEN HD (SEE NOTE #4 & #5 BELOW)	1625	2145	HTT4 w/ (29) 1/2" x 1 1/2" NAILS AND (1) 1/2" x 1 1/2" T.R. EPOXY w/ (2) 3/8" x 4" (SEE NOTE #4 & #5 BELOW)	1510	1835	
Ⓜ	FRAME TO MASONRY	HTT4 w/ (19) 1/2" x 1 1/2" NAILS AND (1) 1/2" x 1 1/2" T.R. EPOXY w/ (2) 3/8" x 4" (SEE NOTE #4 & #5 BELOW)	3420	4225	HTT4 w/ (19) 1/2" x 1 1/2" NAILS AND (1) 1/2" x 1 1/2" T.R. EPOXY w/ (2) 3/8" x 4" (SEE NOTE #4 & #5 BELOW)	3420	4225	
Ⓝ	FRAME TO MASONRY	HTMKT w/ (4) 1/4" x 1/2" SDS WOOD SCREWS & (5) 1/4" x 1/2" TAPCON	785	910	HTMKT w/ (24) 1/4" x 1/2" SDS WOOD SCREWS & (5) 1/4" x 1/2" TAPCON	785	910	
Ⓣ	FRAME TO MASONRY	VGT w/ (16) 1/4" x 3" SDS WOOD SCREWS & (2) 1/2" x 1 1/2" T.R. EPOXY w/ w/ 12" MIN EMBEDMENT	3855	4940	VGT w/ (23) 1/4" x 1/2" NAILS & (4) 1/4" x 3/4" TAPCON	875	1015	
Ⓛ	FRAME TO MASONRY	VGT w/ (32) 1/4" x 3" SDS WOOD SCREWS & (2) 1/2" x 1 1/2" T.R. EPOXY w/ w/ 12" MIN EMBEDMENT	5170	7185	VGT w/ (32) 1/4" x 3" SDS WOOD SCREWS & (2) 1/2" x 1 1/2" T.R. EPOXY w/ w/ 12" MIN EMBEDMENT	5170	7185	
Ⓜ	FRAME TO FRAME	VGT w/ (10) 1/4" x 3" SDS WOOD SCREWS & HTD4-S053 w/ (8) 1/2" NAILS AND (2) 1/2" x 1 1/2" T.R. EPOXY w/ w/ 12" MIN EMBEDMENT	3555	4940	MUG15 w/ (10) 1/2" NAILS & HTT4 w/ (16) 1/2" NAILS & (1) 1/2" x 1 1/2" T.R. EPOXY	-	4160	
Ⓝ	FRAME TO FRAME							

NOT USED

GENERAL CONNECTOR NOTES:
1. CONNECTOR LOCATIONS ARE FOR BRIDGING WOOD NAILS FOR 1/2" x 1 1/2" NAILS.
2. CONNECTOR LOCATIONS ARE PROVIDED BY SIMPSON MANUFACTURER'S CONNECTION PLAN.
3. G.C. MAY USE EITHER SIMPSON OR USP CONNECTIONS. SEE FRAMING PLAN FOR CONNECTOR CALL OUT.
4. CONNECTOR LOCATIONS ARE FOR ALL CONTINUOUS RIM BOARD TO TOP OF MASONRY AT 32" O.C. MAX.
5. CONNECTOR LOCATIONS ARE FOR ALL CONTINUOUS RIM BOARD TO TOP OF MASONRY AT 32" O.C. MAX.
6. SCAD TRUSS CHORD w/ 4-1/2" x 2 3/8" SDS WOOD SCREWS & (2) 10" TOENAILS @ 4" FROM END & 4" O.C.
7. SCAD TRUSS CHORD w/ 4-1/2" x 2 3/8" SDS WOOD SCREWS & (2) 10" TOENAILS @ 4" FROM END & 4" O.C.
8. SCAD TRUSS CHORD w/ 4-1/2" x 2 3/8" SDS WOOD SCREWS & (2) 10" TOENAILS @ 4" FROM END & 4" O.C.
9. SCAD TRUSS CHORD w/ 4-1/2" x 2 3/8" SDS WOOD SCREWS & (2) 10" TOENAILS @ 4" FROM END & 4" O.C.
10. SCAD TRUSS CHORD w/ 4-1/2" x 2 3/8" SDS WOOD SCREWS & (2) 10" TOENAILS @ 4" FROM END & 4" O.C.

Ⓐ MINIMAL CONNECTOR UND ON FRAMING PLAN

1. CONNECTION FOR ALL ROOF / FLOOR TRUSSES TO MASONRY WALLS / UNLEVEL ICW WALLS UND ON PLAN.
2. CONNECTION AT 24" OR 32" C.O. PENDING VERTICALS FOR ALL FLOOR TRUSSES PARALLEL TO MASONRY WALLS.
3. CONNECTION FOR ALL CONTINUOUS RIM BOARD TO TOP OF MASONRY UND ON PLAN.
4. CONNECTION FOR ALL CONTINUOUS RIM BOARD TO TOP OF MASONRY AT 32" O.C. MAX. @ 2" FROM EACH CORNER G.C. TO VERIFY LOCATION DOES NOT CONFLICT W/ T.J. (IF APPLICABLE) LAYOUT
5. CONNECT ALL FLOOR TRUSSES TO INTERIOR BEARING WOOD WALL/BEAMS w/ (2) 10" TOENAILS

Ⓑ MINIMAL CONNECTOR UND ON FRAMING PLAN

1. CONNECTION FOR JACK TRUSS TO WOOD WALL OR BEAM

Ⓒ MINIMAL CONNECTOR UND ON FRAMING PLAN

1. CONNECTION FOR ALL TRUSSES TO INTERIOR/EXTERIOR BEARING WOOD WALLS AND/OR BEAMS

ROOF FRAMING NOTES

1. SHINGLE OR METAL ROOFING SYSTEM (SEE ARCH.) SHEATHING - SEE [RSH] SCHEDULE THIS SHEET. FOR SHGT. SHEATHING & FASTENERS ON PRE-ENGINEERED WOOD TRUSSES AT 2'-0" O.C. MAX. OR CONVENTIONAL FRAME ROOF, SEE PLAN FOR SIZE AND SPACING. SEE ARCHITECTURAL PLAN FOR TYPICAL ROOF SLOPE AND OTHER INFORMATION. TILE ROOFING SYSTEM (SEE ARCH.) SEE [RSH] SCHEDULE THIS SHEET

2. THE EXTERIOR CEILING FOR THE ENTRIES AND PORCHES SHALL HAVE EITHER 7/16" OSB EXPOSURE 1 SHEATHING OR 1/4" DENSGLASS TO THE UNDERSIDE OF THE ROOF TRUSSES. ALL PANEL EDGES ARE TO BE BLOCKED SOLID WITH 2x4 #2 SYP WITH (3) 10" TOENAILS EACH END. THE SHEATHING IS TO BE NAILED WITH 8D NAILS AT 4" ON CENTER AT ALL EDGES AND THEN 8" ON CENTER IN FIELD


3. FOR UNDERLAYMENT REQUIREMENTS SEE R905.1.1.3

-- - - - - NOTE TO FRAMER - - - - -

IF COLD TRUSS LAYOUT SHOWS TRUSS ID'S, THIS LAYOUT IS BEING PROVIDED BY THE COLD TRUSS DESIGNER/ARCHITECT FOR THE DESIGN OF THIS PROJECT. SINCE THIS A GENERIC LAYOUT HAS BEEN DETERMINED, BUT PRIOR TO CONSTRUCTION OR TRUSS FABRICATION, FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS ARE TO BE SUBMITTED TO ENGINEER OF RECORD (E.O.R.) FOR REVIEW AND APPROVAL. AT THIS TIME THE E.O.R. RESERVES THE RIGHT TO REVISE THE PLAN AS REQUIRED PER THE REVIEW OF THE FINAL TRUSS LAYOUT AND TRUSS SHOP DRAWINGS. ADDITIONAL FEE'S MAY APPLY. STARTING CONSTRUCTION OR TRUSS FABRICATION PRIOR TO THIS REVIEW IS NOT ADVISED, AND THE E.O.R. IS NOT RESPONSIBLE FOR ADDITIONAL COSTS DUE TO REVISIONS OF THE PLAN. IF CONVENTIONAL FRAMING IS SHOWN, NO TRUSS APPROVAL IS REQUIRED, UNLESS LAYOUT IS REVISED W/OUT WRITTEN APPROVAL FROM E.O.R.

SEE PLAN SET FOR TRUSS BRACING AND ADDITIONAL ROOF INFORMATION

BLK:	35	UNIT:	
Community:	Preserve at Laurel Lake		
Proj. Name:	2240		
Proj. Address:	520 NW Ballou Dr. Lake City FL		
Proj. No.:	Client No.:		
Sheet No.:	Project No.:		
S-1			
ROOF PLAN B			

















NOTE:
1) SEE TRUSS MANUFACTURER'S TRUSS ENGINEERING CUT SHEETS FOR ADDITIONAL PERMANENT BRACING THAT MAY BE REQUIRED
2) "T" BRACING MAY BE USED IN PLACE OF PERMANENT BRACING PROVIDED IT EXTENDS OVER AT LEAST 90% OF THE WEB.

TB05 REQUIRED MINIMUM PERMANENT TRUSS BRACING PLAN

N.T.S.

RSH		ENGINEERED ROOF PER ASCE 7-22 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT \leq 25 ft	


TB15 EXTERIOR NON-BEARING WALL DETAIL N.T.S.

WC04 GARAGE HEADER ANCHOR 3/4" = 1'-0"

WC05 SECT. OVERHEAD GAR. DOOR INSTALL N.T.S.

WF64 EXTERIOR NON BRDG. WALL DETAIL N.T.S.

WF43 EXTERIOR ANGLED WALL DETAIL N.T.S.

WC03 WALL TO WALL CONN. @ END OF SHEARWALL 1 1/2" = 1'-0"

CD11 COMMON BEAM ATTACHMENT N.T.S.

CD25 BEAM TO WALL CONNECTION N.T.S.

WF66 TYPICAL BEARING WALL N.T.S.

WF09 WALL STEP @ CORNER N.T.S.

WC06 EXTERIOR FRAME CORNER 3/4" = 1'-0"

RD01 VALLEY FLASHING DETAIL N.T.S.

CD26 GIRDER BASE CONNECTION 1/2" = 1'-0"

WF68 CORNER CONNECTION N.T.S.


258 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 800-2333
CARLA A. BROWN, PE - FL # 56126
SCOTT LEWKOWSKI, PE - FL # 78750

100% Employee Owned
myTGSG.com





SIGNATURE & SEAL
9/6/2025

To the best of the Engineers knowledge, information and belief, the structural plans and specifications contained in these drawings comply with the 2023 Florida Building Code - International Edition. The Engineers signature and seal is only for the structural engineering portions of the drawing pages bearing the Engineers signature and seal.

ADAMS HOMES
FLORIDA CONTRACTORS LICENSE NO. CRC1330146
100 WEST GARDEN STREET
PENSACOLA FL 32502
Division location: GAINESVILLE

Lot: 35 Blk: _____ Unit: _____
Community: Preserve at Laurel Lake
Plan Name: 2240
Project Address: 520 SW Bellflower Dr.
Lake City FL
Client No.: _____

Project No.: S-2.1
Sheet No.: S-2.1
TYPICAL FRAMING DETAILS



Project No.: S-2.1
Sheet No.: S-2.1
TYPICAL FRAMING DETAILS



TOTAL SOLUTIONS GROUP
58 Southhall Lane, Suite 200
Maitland, Florida, 32751
(407) 800-2333

CARL A. BROWN, PE - FL # 56126
SCOTT LEWKOWSKI, PE - FL #78750

00% Employee Owned
myTSGhome.com



the best of the Engineer's knowledge, information and belief, the structural plans and specifications contained within these drawings comply with the 2023 IBC Building Code- Residential 8th Edition. The Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing



Dir

This technical diagram illustrates the cross-section of a house's foundation and wall construction, showing the following components and details:

- Foundation:** The foundation is shown with a concrete footer and a backfill area labeled "TREATED, CLEAN, COMPACTED FILL OVER VAPOR BARRIER". A note at the bottom states "SEE FOUNDATION PLAN FOR ACTUAL SIZE AND BAR REQUIREMENTS".
- Grade:** The ground surface is labeled "GRADE".
- Slab:** The top of the foundation is labeled "FINISH FLOOR TOP OF SLAB".
- Brick Veneer:** The exterior wall is made of "COMMON BRICK W/GALV WALL TIES" with "MAX. SPACING 16" O.C. VERT & HORIZ". It includes "PROVIDE WEEP HOLES @ 33" O.C. @ COURSE w/ 1" AIR SPACE BETWEEN" and "HOUSEWRAP VAPOR BARRIER OR EQ OSB AND BRICK VENEER". A note specifies "(SEE SHEET S-1 FOR NAILING SCHED (VERIFY BRICK DIMENSION W/ BLDR))".
- Wall Construction:** The interior wall is framed with "2x STUDS" and "GYP. BD." (drywall). A note says "TAPED AND PAINTED". A callout box states "FRAME WALL USING DETAIL WF66 ON SHEET S-2 @ EXTERIOR WALLS." Another note says "REFER TO ENERGY CALCULATION SHEET FOR INSULATION TYPE & 'R' FACTOR".
- Roof:** The roof is shown with "COMPOSITE SHINGLES INSTALLED PER MFGR. RECOMMENDATIONS OVER APPROVED UNDERLAYMENT PER FBC 905.1.1 OVER APA RATED 7/16" O.S. ROOF SHEATHING INSTALLED PERPENDICULAR TO ROOF TRUSSES OVER ENG. WOOD TRUSSES SEE FRAMING PLAN FOR CONNECTOR SPEC.". It includes "SEE ENERGY FORM CALCULATIONS FOR INSULATION REQUIREMENTS PROVIDE BAFFLES AT EAVE".
- Truss Anchors:** "TRUSS ANCHOR (SEE PLAN) TO BE INSTALLED ON OUTSIDE FACE".
- Floor Plan:** A circular symbol indicates "SEE FLOOR PLAN".
- Brick Support:** "BRICK SUPPORT ABOVE ALL OPENING (TYP.) * SEE DETAIL BD07 ON THIS SHEET".
- Header Information:** "SEE WF66 DET. ON SHEET S-2 FOR HEADER INFO".
- Notes:** "NOTE: 44" MAX. SILL HGT. ON ALL BEDROOMS WINDOWS." and "12" MIN DEPTH BELOW GRADE".

BD12 TYPICAL WALL SECTION

ATIONS W/(1)
ERED 10d
NAILS
3") OR EQUAL

(3) 2 x 4 LAMINATIONS W/ (2)
ROWS OF STAGGERED 16d
COMMON WIRE NAILS
(ONE INTO EACH OUTSIDE FACE)
(D = 0.162", L = 3-1/2") OR EQUAL

LS ARE DRIVEN FROM

3) FOR 4-PLY, PROVIDE 1/4" DIA. x 5 1/2" LAG

TYPICAL COLUMNS DETAILS

12

SEE ELEV

VARIABLES

PRE-ENG. TRUSSES

FOR CONNECTION
SEE ROOF
FRAMING PLAN

BEAM HEADER
SEE FRAMING PLAN

SEE BEAM SCHEDULE
FOR CONNECTION

SEE PLAN FOR COLUMN

SIMPSON ABU44 5/8" ATR
DRILLED & EPOXIED W/ MIN.
7" EMBEDMENT

OPT. STEM WALL
SEE FOUNDATION PLAN
FOR FTG. REQ.

CD24 POST & BEAM DETAIL 1/2" = 1'-0"

**VERIFY BRICK
DIMENSION W/ BLDR.**

3" x 5" ANGLE DETAIL FRONT VIEW

1/2" x 3" LAG SCREWS INTO WOOD HEADER @ 16" O.C. FOR OPENING GREATER THAN 4'-0"

3 1/2"

5"

EXTEND MIN. 6" BEYOND OPNG. TYP. BOTH ENDS

CONT.

4" BRICK [STONE] VENEER TYPICAL

BRICK VENEER TIES NOT OVER 16" O.C. (VERT) & NOT OVER 16" O.C. (HORZ.)

(2) - 2X HEADERS SEE PLAN FOR SIZE

3" x 5" x 1/4" L.L.V. CONT. SHELF ANGLE W/ 1/2" x 3" LAG SCREWS INTO WOOD HEADER @ 16" O.C. FOR OPENINGS GREATER THAN 4'-0"

SHELF ANGLE TO BE GALVANIZED OR COATED TO PREVENT RUSTING G.C. TO COORD.

BD07 BRICK SHELF DETAIL N.T.S.

See plan for t/wall

2x4 support block

(2) 12d nails

(2) 12d toenails

soffit line

wall stud

SECTION A-A

This technical diagram illustrates a wall stud connection. A horizontal 2x4 support block is shown above a wall stud. The support block is secured to the wall stud with two 12d nails. The connection is reinforced with two 12d toenails. The soffit line is indicated by a line with arrows pointing downwards. The wall stud is labeled at the bottom. A note on the left specifies to "See plan for t/wall".

NOTE:
**G.C. SHALL VERIFY SOFFIT MATERIAL CAPACITY
 TO RESIST THE DESIGN PRESSURES SPECIFIED
 PER FBC2020 7th. EDITION R301 FOR THE
 COMPONENTS AND CLADDING WIND PRESSURE.**

2x4 Attached to every other truss and toe nail stud wall through sheathing

2x6 Sub-Facia

See Arch. plans for Fascia

2x4 to bottom of cross 2x4 cont around soffit

Brick Space

2'-0" Overhang

If 1x4 is not applicable contractor shall install 2x4 #2 SPF centered over soffit blocking and attach to min. of (2) stud members w/ (2) 12d nails

Cont. 1x4 #2 SYP attached to each stud w/ min. (2) 10d nails

TYPICAL SOFFIT AND EAVE DETAIL

3/4" = 1

This technical diagram illustrates the construction details for a brick wall at a double bearing point, showing its connection to roof trusses and top plates. The wall is built with 8" thick brick, 7/16" sheathing, and a 12" top plate. The diagram highlights the use of Simpson SPH4 and SP2 connectors, as well as Simpson SP4 bearing plates. It also specifies the use of 16" O.C. wall ties and 1" air space between brick and OSB sheathing. The diagram includes a reference to the framing plan for connectors and the use of Simpson SPH4 for truss bearing.

ROOF SHEATHING

12 SEE PLAN

(2) 2x4 CONT. TOP PLATE

SIMPSON SPH4 EACH STUD

SEE PLAN FOR TRUSS BRG.

FRAMING PLAN CONNECTORS

BRICK W/GALV WALL TIES
16" O.C. VERT & HORIZ.
KEEP HOLES @ 33" O.C. @ FIN. GRADE
1" AIR SPACE BETWEEN BRICK
OSB WALL SHEATHING
(S-1 FOR NAILING SCHEDULE)
CHECK DIMENSION W/ BLDR.)

7/16" SHEATHING

16" O.C. (SEE PLAN)
16" O.C. (SEE PLAN)
16" O.C. (SEE PLAN)
16" O.C. (SEE PLAN)

STA24 EACH STUD

ROOF SHEATHING

TRUSS

SEE PLAN FOR TRUSS BRG.

SEE PLAN FOR CONN.

SIMPSON SP2 EACH STUD

SEE PLAN FOR TRUSS BRG.

SECTION AT DOUBLE BEARING

N.T.S.

This technical diagram illustrates a corner and raised beam construction detail. It shows a vertical column of vertical studs. A horizontal Simpson MSTa24 plate is attached to the studs. A top horizontal plate is labeled '(2) 2X TOP PLATE'. A top horizontal beam is labeled '(2) 2X TOP P'. Arrows point to the Simpson plate, the top plate, and the top beam. A note at the bottom left states: 'ATTACH 2X TO BUILT-UP W/ 2 ROWS OF 12d NAILS STAGGARD @ 8" O.C.' A note on the right side states: '2 X BLOCKING (4) 12d NAIL'.

2 ROWS 8d @ 6" O.C.

8d NAILS @ 6" O.C. TO BLOCKING

(2) SYP#2 TOP PLATE

ROOF OR FLOOR SHEATHING

(2) 12d NAILS TO BLOCKING

SIMPSON SP2

TRUSSES

2X4 BLOCKING AT EA. ROOF PANEL JOINT AT 48" O.C. MAX

LSTA12 EACH SIDE @ EACH END OF WALL



STRUCTURAL SHEATHING (MIN. 7/16"). NAIL w/10d @ 3" O.C. EDGES STAGGERED & 6" O.C. INTERIOR - EXTEND TO ROOF SHEATHING

2x4 SPF STUDS @ 12" O.C.

SIMPSON SP1 OR SPH4

1/2"x 10" A.BOLT 6" FROM ENDS THEN 32" O.C. - OR 5/8" w/7" EMBED WEDGE BOLT 6" FROM END THEN 32" O.C. W/#3 PT SYP BASE PLATE


SEE FND. PLAN FOR FOOTING SPECS.



To the best of the Engineer's knowledge, information and belief, the structural plans and specifications contained in these drawings comply with the 2023 Florida Building Code - Residential Edition. Engineer's signature and seal is only for the structural engineering portions of the drawing pages bearing engineer's signature and seal.




Lot:	35	BLK:	1	UNIT:	
Community:	Reserve at Laurel Lake				
Project Name:	2240				
Project Address:	5251 Bulltower Dr. Laurel Lake City, FL				
Client No.:					




TB01 TYPICAL CROSS BRACING DETAIL

N.T.S.




TB02 TYPICAL CROSS BRACING DETAIL

N.T.S.



TB03 HIP / RIDGE BLOCKING DETAIL


N.T.S.



TB04 TRUSS BRACING OVERLAP DETAIL (TYP)

N.T.S.


THE HEIGHT OF THE CHIMNEY SHOULD EXTEND 2' ABOVE THE POINT WHERE THE CHIMNEY IS 10' FROM THE NEAREST BUILDING SURFACE.



CH01 TYPICAL CHIMNEY FRAME DETAIL


3/4" = 1'-0"

RAFTER SIZE	
0'-8" SPAN -	2"X6" W/4-12d EACH END
8'-12" SPAN -	2"X8" W/4-12d EACH END
12'-15" SPAN -	2"X10" W/ SIMPSON A 34 @ EA. END
15'-18" SPAN -	2"X12" W/ SIMPSON A 34 @ EA. END




TB17 CONV. FRAMING & VALLEY FRAMING

N.T.S.






GEO4 "T" BRACE CONNECTION @ GABLE END W/ VOLUME CEILING

3/4" = 1'-0"




WF05 DORMER FRAMING DETAIL

N.T.S.



TYP. WOOD TRUSS BLOCKING
@ RAISED HEEL DETAIL



A-A ALTERNATE BLOCKING
DETAIL @ INTERIOR BEARING

TB06 BLOCKING AND CONVENTIONAL FRAME DETAILS

3/4" = 1'-0"

GE05 GABLE END BRACING - FRAME WALL N.T.S.

GE22 GABLE END BRACING w/ VOL CEILING 1/2"=1'0"

GE23 GABLE END BRACING w/o VOLUME CEILING 1/2"=1'0"

GE24 GABLE @ VAULT N.T.S.

WF72 LEDGER N.T.S.

WF73 KNEEWALL @ DORMER N.T.S.

GE21 SECTION @ DUTCH GABLE 3/4" = 1'0"

LD02 SHEAR TRANSFER EXTERIOR WALL N.T.S.

GE23.1 GABLE END OVERHANG 1/2"=1'0"

SR01 SECTION AT SHED ROOF 3/4" = 1'0"

GE15 FALSE BEAM AT GABLE END N.T.S.

